



RAIL LAYOUT

SCALE 1" = 10'-0"

NOTES:

- 1. ALL DIMENSIONS ARE ALONG FACE OF RAIL UNLESS OTHERWISE NOTED.

SCHEDULE I		
POST NO.	SPACING	PAYMENT FACTOR
1	3'-1 1/2"	1.4 X 12'-6"
2	3'-1 1/2"	
3	3'-1 1/2"	
4	3'-1 1/2"	
5	3'-1 1/2"	1.2 X 12'-6"
6	4'-2"	
7	4'-2"	
8	4'-2"	1.0 (TYP.)
9	6'-3" (TYP.)	

SCHEDULE II		
POST NO.	SPACING	PAYMENT FACTOR
1	3'-1 1/2"	1.4 X 18'-9"
2	3'-1 1/2"	
3	3'-1 1/2"	
4	3'-1 1/2"	
5	3'-1 1/2"	1.2 X 12'-6"
6	3'-1 1/2"	
7	3'-1 1/2"	
8	4'-2"	1.0 (TYP.)
11	6'-3" (TYP)	

PROJECT NAME: SPRINGFIELD	PLOT DATE: 30-AUG-2011
PROJECT NUMBER: BRO 1442(26)	DRAWN BY: R. PELLETT
FILE NAME: s95j282rail.dgn	CHECKED BY: J. SALVATORI
PROJECT LEADER: K. HIGGINS	SHEET 13 OF 52
DESIGNED BY: J. SALVATORI	
BRIDGE AND APPROACH RAILING SHEET	