

QUANTITY SHEET



| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | | TOTALS | | | DESCRIPTIONS | | | DETAILED SUMMARY OF QUANTITIES | | |
|---------------------------------|-----------------|---------|---------|---------------|---------------|------|-----------------|-------|-------------|--------|------|---|--------------|------------|------|--------------------------------|--|--|
| FULL E&C | EROSION CONTROL | ROADWAY | CHANNEL | ABUTMENT NO.2 | ABUTMENT NO.1 | SLAB | BRIDGE QUANTITY | ROUND | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | QUANTITIES | UNIT | ITEMS | | |
| | 30 | | | | | | | | 30 | | CM | TOPSOIL | 651.35 | | | | | |
| | 130 | | | | | | | | 130 | | SM | GRUBBING MATERIAL | 651.40 | | | | | |
| | 1 | | | | | | | | 1 | | LS | EROSION & SEDIMENT CONTROL PLAN | 652.10 | | | | | |
| | 50 | | | | | | | | 50 | | HR | MONITORING EROSION & SEDIMENT CONTROL PLAN | 652.20 | | | | | |
| | 1 | | | | | | | | 1 | | LU | FIELD MAINT. OF EROSION & SEDIMENT CONTROL PLAN | 652.30 | | | | | |
| | 20 | | | | | | | | 20 | | SM | EROSION MATTING | 654.10 | | | | | |

PROJECT NAME: **WEATHERSFIELD**
 PROJECT NUMBER: **TH3 9514**
 FILE NAME: 95j284 PLOT DATE: 2/5/2004
 PROJECT LEADER: R. WHITCOMB DRAWN BY: S. SCRIBNER
 DESIGNED BY: J. LACROIX CHECKED BY: J. LACROIX
 QUANTITY SHEET #2 SHEET 5 OF 31