STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
1+026.254 RT	ONE LANE BRIDGE	1	750	750	0.563						1			X			X	X															W5-3		SEE DETAIL ON SHEET 34
1+035.151 RT		1	300	900	0.270						1			X			X	X															OM-3R		E-120M
1+035.156 LT		1	300	900	0.270						1			X			X	X															OM-3L		E-120M
1+061.860 LT		1	300	900	0.270						1			X			X	X															OM-3R		E-120M
1+062.252 RT		1	300	900	0.270						1			X			X	X															OM-3L		E-120M
1+089.784 LT	ONE LANE BRIDGE	1	750	750	0.563						1			X			X	X															W5-3		SEE DETAIL ON SHEET 34

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

											m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg									
TOTALS		m^2 2.8	m^2	EA.	m^2						m 22			m 22					kg			EA.	kg				EA.	EA.	kg					

SHEET NAME: SIGN SUMMARY SHEET

PROJECT NAME: CLARENDON
PROJECT NUMBER: BRO 1443(34)

HIGHWAY NO.: TH 16
BRIDGE NO.: 24
OVER: CLARENDON RIVER

FILE NAME: /PW/95J286/sj286sgn.dgn
PROJECT MANAGER: R. WHITCOMB
DESIGNED BY: C. CARLSON
BRIDGE SHEET NUMBER:

PLOT DATE: 01-DEC-2005
DRAWN BY: J. GILMORE
IPARM NAME: sj286sss.i
SHEET 35 OF 43