

# QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES													TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	CHANNEL	SUPER-STRUCTURE	ABUT 1	ABUT 2	APPR SLAB 1	APPR SLAB 2	TRAINING	EROSION CONTROL	FULL E&C	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS		
5								10				15		CM	STONE FILL, TYPE I	613.10					
								10				10		CM	STONE FILL, TYPE I (MOD. 1 - CHECK DAMS)	613.10					
								10				10		CM	STONE FILL, TYPE I (MOD. 2 - STABILIZED CONSTRUCTION ENTRANCE)	613.10					
730	480									480		1210		CM	STONE FILL, TYPE III	613.12					
1												1		EACH	RELOCATE MAIL BOX, SINGLE SUPPORT	617.10					
110												110		M	SNOW FENCE (MOD. - ARCH.)	620.70					
								430				430		M	SNOW FENCE (MOD. - PDF)	620.70					
182												182		M	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	621.21					
4												4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60					
4												4		EACH	GUARD RAIL APPR. SECTION, NETC 2 RAIL	621.72					
102												102		M	TEMPORARY TRAFFIC BARRIER	621.90					
			6	6							12	12		EACH	EARTH PRESSURE CELL	623.60					
50												50		HR	FLAGGERS	630.15					
100												100		HR	FLAGGERS (MOD. - RAILROAD)	630.15					
									1			1		LS	FIELD OFFICE-ENGINEERS	631.10					
									1			1		LS	TESTING EQUIPMENT - CONCRETE	631.16			N.A.B.I. = NOT A BID ITEM		
									1			1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17					
									1			1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25					
							520					520		HR	EMPLOYEE TRAINEESHIP	634.10					
1												1		LS	MOBILIZATION / DEMOBILIZATION	635.11					
1												1		LS	TRAFFIC CONTROL	641.10					
630												630		M	100 mm YELLOW LINE	646.21					
25												25		M	600 mm STOP BAR	646.26					
4												4		EACH	LETTER OR SYMBOL	646.30					
2												2		EACH	RAILROAD CROSSING SYMBOL	646.32					
			170	150							320	320		SM	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR (MOD.)	649.11					
1310	530		250	240							1020	2330		SM	GEOTEXTILE UNDER STONE FILL	649.31					
130												130		SM	GEOTEXTILE FOR UNDERDRAN TRENCH LINING	649.41					
			80	80							160	160		SM	GEOTEXTILE FOR UNDERDRAN TRENCH LINING (MOD.)	649.41					
								545				545		SM	GEOTEXTILE FOR SILT FENCE	649.51					
								110				110		SM	GEOTEXTILE FOR FILTER CURTAIN	649.61					
								20				20		KG	SEED	651.15					
								5				5		KG	SEED-WINTER RYE	651.17					
								130				130		KG	FERTILIZER	651.18					
								1.5				1.5		T	AGRICULTURAL LIMESTONE	651.20					
								1.5				1.5		T	HAYMULCH	651.25					
								140				140		CM	TOPSOIL	651.35					
680	460									460		1140		SM	GRUBBING MATERIAL	651.40					
								1				1		LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10					
								50				50		HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20					
								1				1		LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.30					
															(N.A.B.I.)						
								140				140		SM	EROSION MATTING	654.10					
2.7												2.7		SM	TRAFFIC SIGNS, TYPE A	675.20					
15												15		M	FLANGED CHANNEL SIGN POST	675.301					
15												15		M	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341					
6												6		EACH	REMOVING SIGNS	675.50					
2												2		EACH	ERECTING SALVAGED SIGNS	675.60					

PROJECT NAME: **LEICESTER**  
 PROJECT NUMBER: **BRF 0160 (3) S**  
 FILE NAME: 05j288Structures\sj288qnt.xls PLOT DATE: 04/07/2005  
 PROJECT MANAGER: R. R. WHITCOMB DRAWN BY: G. ROY  
 DESIGNED BY: C. CARLSON CHECKED BY: C. CARLSON  
 QUANTITY SHEET #2 SHEET 5 OF 90