

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	BRIDGE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				EARTHWORK SUMMARY
							400				400		CY	COMMON EXCAVATION	203.15		400	CY	COMMON EXCAVATION (400 x 1.0)
										100	100		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27		75	CY	CHANNEL EXCAVATION (100 x 0.75)
										300	300		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30		420	CY	COFFERDAM EXCAVATION (560 x 0.75)
										560	560		CY	COFFERDAM EXCAVATION, EARTH	208.30		895	CY	SUB TOTAL
										1	1		LS	COFFERDAM (ABUTMENT #1)	208.40		5	CY	ROUND
										1	1		LS	COFFERDAM (ABUTMENT #2)	208.40		900	CY	TOTAL FILL AVAILABLE
														BEGIN OPTION AA			60	CY	TOTAL FILL REQUIRED
							500				500		CY	SUBBASE OF GRAVEL	301.15		840	CY	TOTAL WASTE
							500				500		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25				
							500				500		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
														END OPTION AA					
							140				140		CY	AGGREGATE SURFACE COURSE	401.10				
										96	96		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
										1	1		EACH	REMOVAL OF STRUCTURE (350 SF - EST.)	529.15				
										1	1		LS	PRECAST CONCRETE STRUCTURE (34'-0" x 7'-0" x 25'-4" FRAME OR ARCH TYPE)	540.10				
										1	1		LS	PRECAST CONCRETE STRUCTURE (PEDESTAL WALL ABUTMENT #1)	540.10				
										1	1		LS	PRECAST CONCRETE STRUCTURE (PEDESTAL WALL ABUTMENT #2)	540.10				
														BEGIN OPTION BB					
							12				12		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215				
							12				12		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415				
							12				12		LF	18" CPEP(SL)	601.2615				
														END OPTION BB					
								1			1		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
							5				5		CY	STONE FILL, TYPE I	613.10				
										170	170		CY	STONE FILL, TYPE IV	613.13				
							106				106		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
							4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
							4				4		EACH	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM	621.737				
							50				50		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							200				200		HR	FLAGGERS	630.15				
									1		1		LS	FIELD OFFICE, ENGINEERS	631.10				
									3000		3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
										130	130		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								150			150		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								75			75		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								5			5		LB	SEED	651.15				
								40			40		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				

PROJECT NAME: WOODSTOCK
PROJECT NUMBER: BRO 1444(55)

FILE NAME: s95j294qs.dgn
PROJECT LEADER: K. HIGGINS
DESIGNED BY: J. SALVATORI
QUANTITY SHEET 1

PLOT DATE: 13-FEB-2013
DRAWN BY: J. SALVATORI
CHECKED BY: W. LAMMER
SHEET 4 OF 28