



BILL OF MATERIALS			
DET. #	QTY	DESCRIPTION	MATERIAL
1	10	W6x25 FASCIA MOUNTED POST @ 3' 1"	ASTM A572 Gr. 50
2	2	TS8x4x3/16" TUBING @ 20'-7" w/Cap	ASTM A500 Gr. B
3	2	TS8x4x3/16" TUBING @ 17'-6-1/2" w/Cap	ASTM A500 Gr. B
4	20	TS8x4x3/16" TUBING @ 6'	ASTM A500 Gr. B
5	2	C7x9.8 CHANNEL @ 2' 7" (SPLICE)	ASTM A572 Gr. 50
6	14	5/8"x10" HEX BOLT	ASTM A325
7	14	5/8"x13" HEX BOLT	ASTM A325
8	36	5/8"x1-3/4" HEX BOLT	ASTM A325
9	14	3/16"x1-3/4"x3" SPECIAL WASHER	ASTM A572 Gr. 50
10	64	5/8" HEX NUT	ASTM A563
11	98	5/8" FLAT WASHER	ASTM A436
12	40	1/4"x2"x5" PLATE WASHER	ASTM A572 Gr. 50
13	6	10 GAUGE "W" BEAM @ 12' 6"	AASHTO M180-CI B, TYPE II
14	64	5/8"x1-1/4" SPLICE ROUND HEAD BOLT	ASTM A307
14a	64	5/8" RECESSED NUT for PANEL SPLICE	ASTM A307
15	20	"U" ANCHOR BOLTS	ASTM A449
16	80	1" HEX NUT	ASTM A563
17	80	1" FLAT WASHER	ASTM F436
18	4	DELINEATOR	ALUMINUM

ITEM #: 900.640
 APPROVED BY: [Signature]
 Vermont Agency of Transportation
RECEIVED
 CK'D BY JTS OK'D BY [Signature]
 July 15, 2013
 RESUBMIT NO Approved AsNoted
 BY KMH DATE 7-16-2013

CONTRACTOR: F R LaFayette - 27795 SHEET 1 OF 2

Special Provision Fascia Mounted Steel Bridge Rail
 Town of Woodstock County of Windsor Bridge No. 13

R NO.	DATE	DESCRIPTION	BY	R NO.	DATE	DESCRIPTION	BY
E 1	5/28/13	Added 4ea. W6x25 Post @ 6'-0", one for Each Corner	D.L.	E			
V 2	7/3/13	Implemented Revisions per J.S. on June 23, 2013	D.L.	V			

ELDERLEE, INC.
 OAKS CORNERS, NEW YORK 14518
 E-Mail: dlong@elderlee.com
 Tel: 315-789-6670 Fax: 315-789-8615

DRAWN: D.L. 5/20/13
 CHECKED: E.P. 5/20/13
 APPROVED: [Signature]
 SCALE: SCHEMATIC
 DRAWING NO. F R LAFAYETTE EM13-084R