

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	ROADWAY (NO FED/STATE PARTICIPATION)	EROSION CONTROL	BRIDGE	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						310					310		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	2			
						4					4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
						4					4		EACH	GUARDRAIL APPROACH SECTION, CONC COMB BRIDGE RAILING TL-3	621.748	-			
						250					250		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	1			
						500					500		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	EST.			
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
						520					520		LF	4 INCH WHITE LINE	646.20	2			
						520					520		LF	4 INCH YELLOW LINE	646.21	2			
						△ 1060					1060		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	8.06			
								570			570		SY	GEOTEXTILE UNDER STONE FILL	649.31	7.13			
								100			100		SY	GEOTEXTILE FOR SILT FENCE	649.51	0.46			
								70			70		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	9.08			
								100			100		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61	9.5			
								10			10		LB	SEED	651.15	2.55			
								10			10		LB	SEED, WINTER RYE	651.17	2.55			
								70			70		LB	FERTILIZER	651.18	7.92			
								0.3			0.3		TON	AGRICULTURAL LIMESTONE	651.20	0.05			
								0.3			0.3		TON	HAY MULCH	651.25	0.05			
								80			80		CY	TOPSOIL	651.35	5.3			
								250			250		SY	GRUBBING MATERIAL	651.40	2.53			
								1			1		LS	EPSC PLAN	652.10	-			
								40			40		HR	MONITORING EPSC PLAN	652.20	EST.			
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
								230			230		SY	TEMPORARY EROSION MATTING	653.20	7.38			
								10			10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	EST.			
								30			30		CY	VEHICLE TRACKING PAD	653.35	-			
								750			750		LF	BARRIER FENCE	653.50	1.87			
								230			230		LF	PROJECT DEMARCATION FENCE	653.55	1.88			
						6.91					6.91		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
						46					46		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
						2					2		EACH	REMOVING SIGNS	675.50	-			
							2				2		EACH	SPECIAL PROVISION (PRECAST REINFORCED CONCRETE PERFORATED CATCH BASIN WITH CAST IRON GRATE)	900.620	-			
							40				40		LF	SPECIAL PROVISION (15 INCH UNDERDRAIN PIPE)	900.640	-			
						1					1		LS	SPECIAL PROVISION (CPM SCHEDULE)	900.645	-			
									1		1		LS	SPECIAL PROVISION (QC/QA CLEANING AND PAINTING STRUCTURAL COMPONENTS)	900.645	-			
						1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645	-			

N.A.B.I. = NOT A BID ITEM

PROJECT NAME: COLCHESTER
PROJECT NUMBER: STP 5600 (I2)

FILE NAME: s95j298qs.dgn
PROJECT LEADER: C. CARLSON
DESIGNED BY: N. VANDENBERG
QUANTITY SHEET 2

PLOT DATE: 23-FEB-2015
DRAWN BY: G. ROKES
CHECKED BY: N. VANDENBERG
SHEET 7 OF 53

KEY	DATE	BY	REVISION
△	02/23/2015	VAOT	ADDED PAY ITEM 649.11.