

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
			ROADWAY	TRAINING	EROSION CONTROL	UTILITIES	UTILITIES - NON PART.	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						20				20		LF	DUCTILE IRON PIPE, CEMENT-LINED (16")	629.24				
						20				20		LF	DUCTILE IRON PIPE, CEMENT-LINED (8")	629.24				
						2				2		EACH	GATE VALVE WITH VALVE BOX (8")	629.27				
						1				1		LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM (16")	629.42				
						1				1		LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM (8")	629.42				
			400							400		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
			1500							1500		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
				520						520		HR	EMPLOYEE TRAINEESHIP	634.10				
			1							1		LS	MOBILIZATION / DEMOBILIZATION	635.11				
			1							1		LS	TRAFFIC CONTROL	641.10				
			950							950		LF	4 INCH WHITE LINE	646.20				
			675							675		LF	4 INCH YELLOW LINE	646.21				
			35							35		LF	24 INCH STOP BAR	646.26				
			8							8		EACH	LETTER OR SYMBOL	646.30				
			135							135		LF	CROSSWALK MARKING	646.31				
			1							1		EACH	RAILROAD CROSSING SYMBOL	646.32				
			60							60		LF	TEMPORARY CROSSWALK MARKING	646.700				
						40				40		SY	GEOTEXTILE FOR SILT FENCE	649.51				
						25				25		LB	SEED	651.15				
						125				125		LB	FERTILIZER	651.18				
						0.5				0.5		TON	AGRICULTURAL LIMESTONE	651.20				
						0.5				0.5		TON	HAY MULCH	651.25				
						10				10		CY	TOPSOIL	651.35				
						1				1		LS	EPSC PLAN	652.10				
						80				80		HR	MONITORING EPSC PLAN	652.20				
						1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
						40				40		CY	VEHICLE TRACKING PAD	653.35				
						3				3		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
			100							100		LF	BARRIER FENCE	653.50				
			450							450		LF	PROJECT DEMARCATION FENCE	653.55				
			32							32		SF	TRAFFIC SIGNS, TYPE A	675.20				
			135							135		LF	FLANGED CHANNEL SIGN POST	675.301				
			12							12		EACH	REMOVING SIGNS	675.50				
			4							4		EACH	ERECTING SALVAGED SIGNS	675.60				
			1							1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
			2							2		CY	SPECIAL PROVISION (CORING CONCRETE)	900.608				

PROJECT NAME: BARRE CITY
PROJECT NUMBER: BHF 6000 (15) S

FILE NAME: z95j302qs.dgn
PROJECT LEADER: J.W. TUCKER
DESIGNED BY: A.P. GUYETTE
QUANTITY SHEET #2

PLOT DATE: 2/11/2009
DRAWN BY: A.P. GUYETTE
CHECKED BY: E.P. DETRICK
SHEET 5A OF 56