



The D.S. Brown Company  
300 E. Cherry Street  
North Baltimore, Ohio 45872  
419.257.3561  
Fax: 419.257.2200  
e-mail: dsb@dsbrown.com  
www.dsbrown.com

### Bonding Procedure

The bonding process for laminating PTFE to the fabric pad is as follows:

The fabric pad surface to be bonded is prepared for lamination. A two-part structural grade epoxy is then applied per the manufacture's instructions. The PTFE is cut slightly oversize to account for the possible drift. The PTFE is then applied to the fabric pad and put into a vacuum press at the appropriate pressure for the necessary time period.

Once the fabric pad PTFE is removed from the press, the PTFE is trimmed to plan size and the pads are submitted for quality control review.

Lewis Engineering Company  
4201 Norex Drive  
Chaska, Minnesota 55318  
952.368.2000  
Fax: 952.448.7000

International Division  
57 Pioneer Road  
Singapore 625608  
65.862.8255  
Fax: +65.862.8255  
e-mail:  
dsbrown@moses2.singnet.com.sg

TRANS  
RECEIVED  
OK'D BY JUC  
MAY 18 2009  
APPROVED ✓  
DATE 5/20/09