

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
						290				290		CY	COMMON EXCAVATION	203.15				
								90		90		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							10			10		CY	TRENCH EXCAVATION OF EARTH	204.20				
								70		70		CY	STRUCTURE EXCAVATION	204.25				
								40		40		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
						110				110		CY	SUBBASE OF GRAVEL	301.15				
						40				40		CY	AGGREGATE SURFACE COURSE	401.10				
								50		50		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
								1		1		LS	SHORING SUPERSTRUCTURE	502.10				
								400		400		LB	STRUCTURAL STEEL	506.60				
								7455		7455		LB	EPOXY COATED REINFORCNG STEEL	507.17				
								7.6		7.6		MFBM	STRUCTURAL LUMBER AND TIMBER, UNTREATED	522.20				
								13.5		13.5		MFBM	STRUCTURAL LUMBER AND TIMBER, TREATED	522.25				
								6		6		MFBM	NONSTRUCTURAL LUMBER, UNTREATED	522.30				
								1		1		LS	STRUCTURAL GLUED LAMINATED TIMBER (8.7 MFBM) (DECK PANELS)	522.40				
								1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
								54		54		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS II	580.14				
								12		12		CY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS III	580.15				
						40				40		CY	STONE FILL, TYPE I	613.10				
								200		200		CY	STONE FILL, TYPE IV	613.13				
						123				123		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
						1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1				1		LS	TRAFFIC CONTROL	641.10				
								200		200		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							50	50		100		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							10			10		LB	SEED	651.15				
							50			50		LB	FERTILIZER	651.18				
							25			25		TON	AGRICULTURAL LIMESTONE	651.20				
							25			25		TON	HAYMULCH	651.25				
							1			1		LS	EPSC PLAN	652.10				
							30			30		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							1400			1400		SY	PERMANENT EROSION MATTING	653.21				
							10			10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
							30			30		CY	VEHICLE TRACKING PAD	653.35				
							620			620		LF	PROJECT DEMARCATION FENCE	653.55				

PROJECT NAME: **WEATHERSFIELD**  
PROJECT NUMBER: **BHO 1442(29)**  
FILE NAME: /96j234/str/s96j234qs.xls PLOT DATE: 02/22/2007  
PROJECT MANAGER: W. SYMONDS DRAWN BY: R. PELLETT  
DESIGNED BY: G. SHANGRAW CHECKED BY: T. SUMNER  
QUANTITY SHEET #1 SHEET 4 OF 60