

COMPOSITE QUANTITY SHEET 1



CHITTENDEN STP 1443(45)				CHITTENDEN STP 1443(46)				TOTALS			DESCRIPTIONS		
ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER
0.5				0.5					1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10
670				740					1410		CM	COMMON EXCAVATION	203.15
		290				90			380		CM	UNCLASSIFIED CHANNEL EXCAVATION	203.27
110				100					210		CM	SAND BORROW	203.31
20				50					70		CM	GRANULAR BORROW	203.32
10	10			10	10				40		CM	TRENCH EXCAVATION OF EARTH	204.20
		250				200			450		CM	GRANULAR BACKFILL FOR STRUCTURES	204.30
		410				310			720		CM	COFFERDAM EXCAVATION,EARTH	208.30
		135				105			240		CM	COFFERDAM EXCAVATION,ROCK	208.35
		1							1		LS	COFFERDAM (STA. 1+061.5)	208.40
		1							1		LS	COFFERDAM (STA. 1+070)	208.40
						1			1		LS	COFFERDAM (STA. 1+221)	208.40
						1			1		LS	COFFERDAM (STA. 1+226.8)	208.40
390				430					820		CM	SUBBASE OF GRAVEL	301.15
140				130					270		CM	AGGREGATE SURFACE COURSE	401.10
		178				118			296		CM	CONCRETE, HIGH PERFORMANCE CLASS B	501.34
		10190				6170			16360		KG	REINFORCING STEEL	507.15
		3600				3180			6780		KG	EPOXY COATED REINFORCING STEEL	507.17
		70				47			117		L	WATER REPELLENT, SILANE	514.10
		31				23			54		M	BRIDGE RAILING, GALVANIZED HD STEEL BEAM/FASCIA MOUNTED	525.41
1									1		LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10
						1			1		LS	ONE-WAY TEMPORARY BRIDGE (44 SM - EST.)	528.10
		1							1		EACH	PARTIAL REMOVAL OF STRUCTURE (BRIDGE 19)	529.20
						1			1		EACH	PARTIAL REMOVAL OF STRUCTURE (BRIDGE 20)	529.20
												BEGIN OPTION AA	
15				11					26		M	450 CAAP 1.52 (68 X 12)	601.0215
15				11					26		M	450 PCCSP 1.63 (68 X 12)	601.0415
15				11					26		M	450 CPEP(SL)	601.2615
												END OPTION AA	
1				1					2		CM	DUST CONTROL WITH WATER	609.10
30				40					70		CM	STONE FILL, TYPE I	613.10
		260				160			420		CM	STONE FILL, TYPE IV	613.13
2									2		EACH	YIELDING MARKER POSTS	619.17
54				50					104		M	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21
4				4					8		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60
100				100					200		HR	FLAGGERS	630.15
			0.5				0.5		1		LS	FIELD OFFICE-ENGINEERS	631.10
			0.5				0.5		1		LS	TESTING EQUIPMENT - CONCRETE	631.16
			0.5				0.5		1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25
0.5				0.5					1		LS	MOBILIZATION / DEMOBILIZATION	635.11
1									1		LS	TRAFFIC CONTROL (STP 1443(45))	641.10
				1					1		LS	TRAFFIC CONTROL (STP 1443(46))	641.10
90		255		140		170			655		SM	GEOTEXTILE UNDER STONE FILL	649.31