STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL 1.7 kg/m	3.0	4.5	SQUARE STEEL (mm) 44 3.4 kg/m	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 1.9 kg/m	100 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) 75 11.3 kg/m	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
0+966.000 LT	STOP	1	750	750	.563						1			X																			RI-1		E-153
092 1+~~100.~~000 LT		1	750	750	.563						1			X																			W3-1		E-150

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

									m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg												
											8.30																									
TOTALS	m^2 1.126	m^2	EA.	m^2		m 8.30			m						kg			EA.	kg			EA.	EA.	kg												

PROJECT NAME:	CABOT
PROJECT NUMBER:	BRO 1446 (27)

FILE NAME:	96J270/structures/sj270tss.dgn	PLOT DATE:	07-DEC-2007
PROJECT LEADER:	C. P. WILLIAMS	DRAWN BY:	J. HUSSEY
DESIGNED BY:	K. M. HIGGINS	CHECKED BY:	K. M. HIGGINS
TRAFFIC SIGN SUMMARY SHEET		SHEET 12	OF 42