

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	EROSION CONTROL	BRIDGE	FILL/CE ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
						1400				1400		CY	COMMON EXCAVATION	203.15				
								1420		1420		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
								140		140		CY	STRUCTURE EXCAVATION	204.25				
								200		200		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
						650				650		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
						180				180		CY	AGGREGATE SURFACE COURSE	401.10				
								70		70		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
								180		180		LF	PRE-EXCAVATION OF INTEGRAL ABUTMENT PILES	503.20				
								1		1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10				
								270		270		LF	STEEL PILING FOR INTEGRAL ABUTMENTS, HP 12 X 84	505.265				
								6		6		EACH	DYNAMIC PILE LOADING TEST	505.45				
								80100		80100		LB	STRUCTURAL STEEL, PLATE GIRDER	506.55				
								10480		10480		LB	REINFORCING STEEL	507.15				
								21350		21350		LB	EPOXY COATED REINFORCING STEEL	507.17				
								1		1		LS	SHEAR CONNECTORS (64" X 7")	508.15				
								100		100		GAL	WATER REPELLENT, SILANE	514.10				
						1				1		LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10				
						1				1		EACH	REMOVAL OF STRUCTURE (2300 SF - EST)	529.15				
						1				1		EACH	REMOVAL OF STRUCTURE 900 SF - EST. (TEMPORARY BRIDGE)	529.15				
								6		6		EACH	BEARING DEVICE ASSEMBLY, ELASTOMERIC PAD	531.11				
							1			1		MGAL	DUST CONTROL WITH WATER	609.10				
						60				60		CY	STONE FILL, TYPE II	613.11				
						640				640		CY	STONE FILL, TYPE II	613.12				
						46				46		LF	REMOVING AND RESETTING FENCE	620.50				
						215				215		LF	BOX BEAM GUARDRAIL	621.30				
						238				238		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
						1				1		LS	MOBILIZATION/DEMOLITION	635.11				
							800			800		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							210			210		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							80			80		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							400			400		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							20			20		LB	SEED	651.15				
							100			100		LB	FERTILIZER	651.18				
							0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20				
							0.5			0.5		TON	HAYMULCH	651.25				
							500			500		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN	652.10				