

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								85			85		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								128			128		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								51			51		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								10			10		LB	SEED	651.15				
								10			10		LB	SEED-WINTER RYE	651.17				
								100			100		LB	FERTILIZER	651.18				
								0.25			0.25		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								32			32		CY	TOPSOIL	651.35				
									140		140		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								5			5		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								600			600		SY	TEMPORARY EROSION MATTING	653.20				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								400			400		LF	BARRIER FENCE	653.50				
								370			370		LF	PROJECT DEMARCATION FENCE	653.55				
							4				4		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				
							1				1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645				

PROJECT NAME:	STAMFORD
PROJECT NUMBER:	STP 1441 (29)
FILE NAME:	s96j226qty.dgn
PROJECT LEADER:	C.W. CARLSON
DESIGNED BY:	H. SALLS
QUANTITY SHEET 2	
PLOT DATE:	24-DEC-2015
DRAWN BY:	D.KARABEGOVIC
CHECKED BY:	H. SALLS
SHEET	7 OF 44