

QUANTITY SHEET 2



SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	UTILITIES	BRIDGE	FULL E & C ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						40	10				50		CM	STONE FILL, TYPE I	613.10				
									630		630		CM	STONE FILL, TYPE IV	613.13				
						255					255		M	CAST-IN PLACE CEMENT CONCRETE CURB, TYPE B	616.28				
						385					385		SM	PORTLAND CEMENT CONCRETE SIDEWALK, 125 MM	618.10				
						6					6		SM	DETECTABLE WARNING SURFACE	618.30				
						4					4		EACH	YIELDING MARKER POSTS	619.17				
						17					17		M	PLANK RAIL	621.15				
						10					10		M	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
								2			2		EACH	ADJUST ELEVATION OF VALVE BOX	629.20				
								7			7		M	DUCTILE IRON PIPE, CEMENT-LINED (150 mm)	629.24				
								1			1		EACH	HYDRANT, RELOCATE	629.29				
								1			1		EACH	TAPPING SLEEVE AND VALVE WITH VALVE BOX (400 mm X 150 mm)	629.35				
						100					100		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						500					500		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE-ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT - CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17				
										1	1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25				
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1					1		LS	TRAFFIC CONTROL	641.10				
						250					250		M	100 MM WHITE LINE	646.20				
						272					272		M	100 MM YELLOW LINE	646.21				
						17					17		M	600 MM STOP BAR	646.26				
						16					16		EACH	LETTER OR SYMBOL	646.30				
						43					43		M	CROSSWALK MARKING	646.31				
						21					21		SM	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
						110			780		890		SM	GEOTEXTILE UNDER STONE FILL	649.31				
							35				35		SM	GEOTEXTILE FOR SILT FENCE	649.51				
							89				89		SM	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							160				160		SM	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							20				20		KG	SEED	651.15				
							20				20		KG	SEED-WINTER RYE	651.17				
							90				90		KG	FERTILIZER	651.18				
							1				1		T	AGRICULTURAL LIMESTONE	651.20				
							1				1		T	HAYMULCH	651.25				
							230				230		CM	TOPSOIL	651.35				
							580				580		SM	GRUBBING MATERIAL	651.40				
							1				1		LS	EPSC PLAN	652.10				
							30				30		HR	MONITORING EPSC PLAN	652.20				
							1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				

N.A.B.I.= NOT A BID ITEM

PROJECT NAME:	BRATTLEBORO
PROJECT NUMBER:	BRF 2000(21)S
FILE NAME: 96j228/structures/sj228qty.dgn	PLOT DATE: 05/22/2009
PROJECT LEADER: R. WHITCOMB	DRAWN BY: D. PETERSON
DESIGNED BY: C. CARLSON	CHECKED BY: C. CARLSON
QUANTITY SHEET #2	SHEET 5 OF 77