STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET (2)

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.6	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
10+160.7 LT.	GUILFORD ST.	1	1050	200	0.21	.	.	.	.	.	1	.	.	.	.	X	.	X	.	.	.	.	.	.	.	.	.	.	.	.	.	.	D-3	.	SHS
.	WESTERN AVE.	1	1050	200	0.21	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	D-3	.	SHS
.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.
10+161.8 RT.	STOP	1	750	750	0.56	.	.	.	.	.	1	.	.	.	.	X	.	X	.	.	.	.	.	.	.	.	.	.	.	.	.	.	R1-1	.	SHS
.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3+064.8 RT.		.	.	.	.	.	1	.	.	.	1	.	.	.	.	X	.	X	.	.	.	.	.	.	.	.	.	.	.	.	.	.	SALVAGE SIGN FROM 3+046.9 RT.	.	.
.		.	.	.	.	.	1	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	SALVAGE SIGN FROM 3+046.9 RT.	.	.
.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3+124 RT.	EAST	1	600	300	0.18	.	.	.	.	.	1	.	.	.	.	X	.	X	.	.	.	.	.	.	.	.	.	.	.	.	.	.	M3-2	.	E-136BM
.	VERMONT 9	1	600	600	0.36	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	M1-5	.	E-136BM
.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.
3+066.8 LT.		.	.	.	.	.	1	.	.	.	1	.	.	.	.	X	.	X	.	.	.	.	.	.	.	.	.	.	.	.	.	.	SALVAGE SIGN FROM 3+041.62 LT.	.	.
.		.	.	.	.	.	1	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	SALVAGE SIGN FROM 3+041.62 LT.	.	.
.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.
.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	.	SHS = STANDARD HIGHWAY SIGNS BOOK	.	.

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS.

TOTALS FROM THIS SHEET	1.52		4								m	m	m	m	m 19.46	m		EA	kg	kg	kg		kg	kg	kg	kg								
															19.46																				
TOTALS FROM SHEET 9	2.08														15.60																				
ROUNDING	m² 0.40	m²	EA.	m²							m				m 0.94				kg			EA.	kg				EA.	EA.	kg					
TOTALS	4.00		4												36.00																				

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: BRF 2000 (21)S

FILE NAME: 96J228\Structures\sJ228tss2.1
PROJECT MANAGER: R. R. WHITCOMB
DESIGNED BY: C. CARLSON
PLOT DATE: 26-MAY-2009
DRAWN BY: D. PETERSON
CHECKED BY: C. CARLSON
SHEET 10 OF 77