

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							340				340		CY	COMMON EXCAVATION	203.15				
									10		10		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							20				20		CY	EARTH BORROW	203.30		58	CY	COMMON FILL(1.15*50 CY)
							70				70		CY	SAND BORROW	203.31				FILL AVAILABLE
									20		20		CY	STRUCTURE EXCAVATION	204.25		306	CY	COMMON EXCAVATION(0.9*340 CY)
									20		20		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30		3	CY	UNCLASSIFIED CHANNEL EXCAVATION(0.3*10 CY)
							520				520		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10		6	CY	STRUCTURE EXCAVATION(0.3*20 CY)
							250				250		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
							20				20		CY	AGGREGATE SURFACE COURSE	401.10				
							3				3		CWT	EMULSIFIED ASPHALT	404.65				
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
									6		6		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
									430		430		LB	STRUCTURAL STEEL	506.60				
									327		327		LB	REINFORCING STEEL	507.15				
									1		1		GAL	WATER REPELLENT, SILANE	514.10				
									24.8		24.8		MFBM	STRUCTURAL LUMBER AND TIMBER, UNTREATED	522.20				
									9.6		9.6		MFBM	STRUCTURAL LUMBER AND TIMBER, TREATED	522.25				
									4.9		4.9		MFBM	NONSTRUCTURAL LUMBER, UNTREATED	522.30				
									1.5		1.5		MFBM	NONSTRUCTURAL LUMBER, TREATED	522.35				
									1		1		LS	STRUCTURAL GLUED LAMINATED TIMBER (10.1 MFBM)(DECK PANELS)	522.40				
									1		1		LS	STRUCTURAL GLUED LAMINATED TIMBER (3.3 MFBM)(CHORDS)	522.40				
									1		1		LS	STRUCTURAL GLUED LAMINATED TIMBER (7.9 MFBM)(FLOORBEAMS)	522.40				
							1				1		LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10				
									1		1		EACH	PARTIAL REMOVAL OF STRUCTURE (TH 2 - BRIDGE NO. 17)	529.20				
									1		1		EACH	PARTIAL REMOVAL OF STRUCTURE (TH 47 - BRIDGE NO. 50)	529.20				
									5		5		CY	REMOVAL OF CONCRETE OR MASONRY	529.25				
							20				20		HR	ROADWAY PATROL MAINTENANCE	607.10				
							10				10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
							3				3		MGAL	DUST CONTROL WITH WATER	609.10				
							12				12		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
							10		10		20		CY	STONE FILL, TYPE I	613.10				
							185				185		LF	STEEL BACKED TIMBER GUARDRAIL	621.18				
							200				200		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							100				100		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							300				300		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				