

QUANTITY SHEET 3

SUMMARY OF BRIDGE QUANTITIES										TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES			
						DECK BR 50	DECK BR 17	ABUTMENT 1	ABUTMENT 2	CHANNEL	BRIDGE TOTAL		UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
								10			10		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27			
								20			20		CY	STRUCTURE EXCAVATION	204.25			
								20			20		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30			
								5	1		6		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34			
								430			430		LB	STRUCTURAL STEEL	506.60			
								327			327		LB	REINFORCING STEEL	507.15			
								1			1		GAL	WATER REPELLENT, SILANE	514.10			
							24.8				24.8		MFBM	STRUCTURAL LUMBER AND TIMBER, UNTREATED	522.20			
						5	4.6				9.6		MFBM	STRUCTURAL LUMBER AND TIMBER, TREATED	522.25			
							4.9				4.9		MFBM	NONSTRUCTURAL LUMBER, UNTREATED	522.30			
							1.5				1.5		MFBM	NONSTRUCTURAL LUMBER, TREATED	522.35			
							1				1		LS	STRUCTURAL GLUED LAMINATED TIMBER (10.1 MFBM)(DECK PANELS)	522.40			
							1				1		LS	STRUCTURAL GLUED LAMINATED TIMBER (3.3 MFBM)(CHORDS)	522.40			
							1				1		LS	STRUCTURAL GLUED LAMINATED TIMBER (7.9 MFBM)(FLOORBEAMS)	522.40			
							1				1		EACH	PARTIAL REMOVAL OF STRUCTURE (TH 2 - BRIDGE NO. 17)	529.20			
						1					1		EACH	PARTIAL REMOVAL OF STRUCTURE (TH 47 - BRIDGE NO. 50)	529.20			
								1	4		5		CY	REMOVAL OF CONCRETE OR MASONRY	529.25			
								10			10		CY	STONE FILL, TYPE I	613.10			
								140			140		SY	GEOTEXTILE UNDER STONE FILL	649.31			
								140			140		SY	GRUBBING MATERIAL	651.40			
							1				1		LS	TIMBER PAINTING, ENVIRONMENTAL PROTECTION	660.10			
							1				1		LS	TIMBER PAINTING, FIRE RETARDANT	660.20			
							1				1		LS	TIMBER PAINTING, INSECTICIDE/FUNGICIDE	660.30			
							402				402		SY	METAL ROOFING	661.10			
							2				2		EACH	REMOVING SIGNS	675.50			
							2				2		EACH	ERECTING SALVAGED SIGNS	675.60			