

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES											TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES							
											EMPLOYEE TRAINERSHIP	ROADWAY	EROSION CONTROL	FULL E&C	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
												1					1		LS	CLEARING AND GRUBBING (INCLUDING INDIVIDUAL TREES AND STUMPS)	201.10			
												1480					1480		CY	COMMON EXCAVATION	203.15			
															430		430		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27			
												370					370		CY	SAND BORROW	203.31			
													5				5		CY	TRENCH EXCAVATION OF EARTH	204.20			
															700		700		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30			
															1210		1210		CY	COFFERDAM EXCAVATION, EARTH	208.30			
															130		130		CY	COFFERDAM EXCAVATION, ROCK	208.35			
															1		1		LS	COFFERDAM (STA. 13+83)	208.40			
															1		1		LS	COFFERDAM (STA. 15+00)	208.40			
												1250					1250		CY	SUBBASE OF CRUSHED GRAVEL (COARSE GRADED)	301.25			
												2					2		CWT	EMULSIFIED ASPHALT	404.65			
												305					305		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.27			
															293		293		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34			
															1		1		LS	SHORING SUPERSTRUCTURE (MOD.)	502.10			
															1		1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10			
															1624		1624		LF	STEEL PILING (HP 14 X 73)	505.17			
															600		600		LB	STRUCTURAL STEEL	506.60			
															44940		44940		LB	REINFORCING STEEL	507.15			
															1		1		LS	STRUCTURAL PAINTING, FIELD APPLIED (MOD.)	513.30			
															1		1		LS	CONTAINMENT & ENVIRON. PROTECTION, FIELD (MOD.)	513.36			
															30		30		GAL	WATER REPELLENT	514.10			
															9		9		MFBM	STRUCTURAL LUMBER AND TIMBER - UNTREATED	522.20			
															20.5		20.5		MFBM	STRUCTURAL LUMBER AND TIMBER - TREATED	522.25			
															8.5		8.5		MFBM	NON - STRUCTURAL LUMBER-UNTREATED	522.30			
															1		1		LS	STRUCTURAL GLUED LAMINATED TIMBER (BOTTOM CHORD)	522.40			
															1		1		LS	STRUCTURAL GLUED LAMINATED TIMBER (FLOOR BEAM)	522.40			
															1		1		LS	MAINTENANCE OF TRAFFIC FOR BRIDGE PROJECTS	527.10			
															1		1		EACH	REMOVAL OF STRUCTURE (MOD. 1)	529.15			
															1		1		EACH	REMOVAL OF STRUCTURE (MOD. 2)	529.15			
															1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20			
															2		2		EACH	BEARING DEVICE ASSEMBLY (MOD.)	531.10			
															177		177		SY	STONE MASONRY FACING (MOD.)	602.25			
													1				1		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25			
												0.5					0.5		TON	DUST & ICE CONTROL WITH CALCIUM CHLORIDE	609.15			
													3				3		CY	STONE FILL, TYPE I	613.10			
															460		460		CY	STONE FILL, TYPE IV	613.13			
												65					65		LF	REMOVING AND RESETTING FENCE	620.50			
												273					273		LF	HVY DUTY STEEL BEAM GUARD RAIL	621.21			
												4					4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60			

ADDENDUM #1

PROJECT NAME:	PROCTOR-PITTSFORD		
PROJECT NUMBER:	BHO 1443 (37)		
FILE NAME:	96j242.xls	PLOT DATE:	10/21/2002
PROJECT LEADER:	C.P.WILLIAMS	DRAWN BY:	str4
DESIGNED BY:	W.B.SYMONDS	CHECKED BY:	W.B.SYMONDS
QUANTITY SHEET #1		SHEET 4 OF 60	