



- NOTES:**
1. THE CONTRACTOR SHALL PREPARE FOR THE PRECONSTRUCTION MEETING A SITE SPECIFIC EROSION CONTROL PLAN FOR THIS PROJECT. THE EROSION CONTROL PLAN SHALL BE APPROVED BY THE RESIDENT ENGINEER AND THE STREAM ALTERATION ENGINEER.
 2. THE EROSION CONTROL PLAN SHALL DESCRIBE THE ACTUAL LOCATION AND TYPES OF CONTROLS THAT ARE TO BE IMPLEMENTED DURING CONSTRUCTION. THE CONTROLS SHOULD ADDRESS EROSION FROM THE INITIAL CLEARING STAGE TO THE FINAL STABILIZATION OF THE SITE. THE PLAN SHOULD REFERENCE STANDARDS T-1 AND T-2 WHEN APPROPRIATE. SPECIAL RESOURCES SUCH AS WETLANDS, AND SURFACE WATERS SHALL BE CLEARLY SHOWN ALONG WITH PROTECTION MEASURES. THE PLANS SHALL INCLUDE BASIC DRAINAGE INFORMATION SUCH AS DRAINAGE PATTERNS, DRAINAGE AREAS, AND THE SIZE AND LOCATION OF DRAINAGE STRUCTURES.
 3. SEDIMENT TRAPPING MEASURES MAY BE REQUIRED FOR CLARIFICATION OF WATER DRAINING FROM THE PROJECT. ALL SEDIMENT THAT IS TRAPPED SHALL BE REMOVED FROM THE PROJECT AND THE GROUND RESTORED TO ITS ORIGINAL SLOPES OR GRADED AS SHOWN ON THE CONSTRUCTION DRAWINGS.
 4. THE CONTRACTOR SHALL USE TEMPORARY OR PERMANENT EROSION CONTROL MEASURES AS NECESSITATED BY THE SEQUENCE OF CONSTRUCTION OR AS ORDERED BY THE RESIDENT ENGINEER. SEE SECTION 105.23 OF THE VERMONT AGENCY OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION DATED 2001.

EROSION CONTROL

SCALE 1" = 20'-0"
 20 0 20

LEGEND	
	SILT FENCE
	FILTER CURTAIN
	HAY BALES

DATUM
 VERTICAL NAVD 88
 HORIZONTAL NAD 83/92

POB
 Sta 10+00.00

PROJECT: PROCTOR - PITTSFORD	PROJECT NO.: BHO 1443 (37)
DESIGN FILE NAME: 961242\Structures\s\242eero.dgn	PLOT DATE: 10-JAN-2003
IPARM FILE NAME: s\242eero.i	SURVEY DATE: 02-02-98
SURVEYED BY: L. ORVIS	DRAWN BY: T. ANDERSON
SQUAD LEADER: C.P. WILLIAMS	SHEET: 15 OF 60
EROSION CONTROL SHEET	