

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					ROADWAY	ROADWAY (NO FED/STATE PART.)	EROSION CONTROL	UTILITIES - BID ITEMS	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								2			2		EACH	GATE VALVE WITH VALVE BOX (6")	629.27				
					480						480		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
					1						1		LS	MOBILIZATION/DEMobilIZATION	635.11				
					850	800					1650		LF	4 INCH YELLOW LINE	646.21				
						27					27		LF	DURABLE 24 INCH STOP BAR	646.480				
					850	880					1730		LF	TEMPORARY 4 INCH YELLOW LINE	646.610				
									270		270		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							95				95		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							60				60		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							15				15		LB	SEED	651.15				
							10				10		LB	SEED, WINTER RYE	651.17				
							90				90		LB	FERTILIZER	651.18				
							0.4				0.4		TON	AGRICULTURAL LIMESTONE	651.20				
							0.3				0.3		TON	HAY MULCH	651.25				
							100				100		CY	TOPSOIL	651.35				
									55		55		SY	GRUBBING MATERIAL	651.40				
							1				1		LS	EPSC PLAN	652.10				
							50				50		HR	MONITORING EPSC PLAN	652.20				
							1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							310				310		SY	TEMPORARY EROSION MATTING	653.20				
							60				60		CY	VEHICLE TRACKING PAD	653.35				
							220				220		LF	BARRIER FENCE	653.50				
							570				570		LF	PROJECT DEMARCATION FENCE	653.55				
					1						1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
									22		22		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)(FPQ)	900.608				
								2			2		EACH	SPECIAL PROVISION (SANITARY SEWER MANHOLE, ALL-INCLUSIVE) (4' DIA.)	900.620				
									106		106		LF	SPECIAL PROVISION (BRIDGE RAILING, TEXAS) (FPQ)	900.640				
								335			335		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT-LINED, ALL-INCLUSIVE) (12" SEWER)	900.640				
								88.7			88.7		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT-LINED, ALL-INCLUSIVE) (8" WATER ON BRIDGE)	900.640				
								157.8			157.8		LF	SPECIAL PROVISION (DUCTILE IRON PIPE, CEMENT-LINED, ALL-INCLUSIVE) (8" WATER)	900.640				
								260			260		LF	SPECIAL PROVISION (TRANSITE PIPE REMOVAL)	900.640				
					1						1		LS	SPECIAL PROVISION (CPM SCHEDULE)	900.645				
					1						1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
					1						1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)	900.650				

PROJECT NAME: RUTLAND CITY  
PROJECT NUMBER: BRF 3000(18)

FILE NAME: s96j244qty.dgn  
PROJECT LEADER: C. CARLSON  
DESIGNED BY: M. EVANS-MONGEON  
QUANTITY SHEET 2

PLOT DATE: 24-MAR-2014  
DRAWN BY: M. LONGSTREET  
CHECKED BY: M. E-M  
SHEET 6 OF 44