

QUANTITY SHEET 1

WOODSTOCK BHO 1444 (52)					WOODSTOCK ST 1444 (58)					SUMMARY OF ESTIMATED QUANTITIES						DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	EROSION CONTROL	FULL CE ITEMS	BRIDGE	BRIDGE	ROADWAY	TRAINING	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
5										5		EACH	REMOVING MEDIUM TREES	201.15	-			
						45				45		CY	COMMON EXCAVATION	203.15	-			
		6								6		CY	TRENCH EXCAVATION OF EARTH	204.20	-			
1										1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
						80				80		CY	STRUCTURE EXCAVATION	204.25	-			
						475				475		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	-			
						400				400		CY	COFFERDAM EXCAVATION, EARTH	208.30	-			
						1275				1275		CY	COFFERDAM EXCAVATION, ROCK	208.35	-			
				1						1		LS	COFFERDAM (EAST ABUTMENT)	208.40	-			
				1						1		LS	COFFERDAM (PIER)	208.40	-			
					1					1		LS	COFFERDAM (WEST ABUTMENT)	208.40	-			
190										190		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-			
						35				35		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25	-			
1										1		CWT	EMULSIFIED ASPHALT	404.65	-			
1										1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
				24	243					267		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34	-			
				0.5	0.5					1		LS	SHORING SUPERSTRUCTURE	502.10	-			
				1						1		LS	STRUCTURAL STEEL	506.75	-			
				3120	20757					23877		LB	REINFORCING STEEL, LEVEL I	507.11	-			
				40	60					100		LF	DRILLING AND GROUTING DOWELS	507.16	-			
				5	5					10		GAL	WATER REPELLENT, SILANE	514.10	-			
				23.5						23.5		MFBM	STRUCTURAL LUMBER AND TIMBER, UNTREATED	522.20	-			
				37.38						37.38		MFBM	STRUCTURAL LUMBER AND TIMBER, TREATED	522.25	-			
				8.92						8.92		MFBM	NONSTRUCTURAL LUMBER, UNTREATED	522.30	-			
				1						1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20	-			
					60					60		CY	CONCRETE, CLASS C	541.30	-			
					90					90		CY	REBUILT STONE MASONRY	602.35	-			
		1								1		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	-			
		2								2		CY	STONE FILL, TYPE I	613.10	-			
						12				12		CY	STONE FILL, TYPE II	613.11	-			
						140				140		CY	STONE FILL, TYPE IV	613.13	-			
						45				45		CY	GABION WALL	613.25	-			
						4				4		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	-			
200										200		LF	STEEL BACKED TIMBER GUARDRAIL	621.18	-			
90										90		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
7										7		EACH	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	-			
80										80		LF	TEMPORARY TRAFFIC BARRIER	621.90	-			
80										80		HR	FLAGGERS	630.15	-			
			0.5						0.5	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
			0.5						0.5	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			

PROJECT NAME: WOODSTOCK WOODSTOCK
PROJECT NUMBER: BHO 1444(52) ST 1444(58)

FILE NAME: z96j262quant.dgn
PROJECT LEADER: M. Sargent
DESIGNED BY: S. Delia
QUANTITY SHEET *1

PLOT DATE: 23-JUL-2012
DRAWN BY: P. Dustin
CHECKED BY: R. Joy
SHEET 5 OF 68

