

# QUANTITY SHEET 2

WOODSTOCK BHO 1444 (52)					WOODSTOCK ST 1444 (58)					SUMMARY OF ESTIMATED QUANTITIES						DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	EROSION CONTROL	FULL CE ITEMS	BRIDGE	BRIDGE	ROADWAY	TRAINING	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
			3000							3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
	260						260			520		HR	EMPLOYEE TRAINEESHIP	634.10	-			
0.5						0.5				1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
1										1		LS	TRAFFIC CONTROL	641.10	-			
		50								50		SY	GEOTEXTILE UNDER STONE FILL	649.31	-			
		10								10		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	-			
		90								90		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61	-			
		11								11		LB	SEED	651.15	-			
		2								2		LB	SEED, WINTER RYE	651.17	-			
		87								87		LB	FERTILIZER	651.18	-			
		0.1								0.1		TON	AGRICULTURAL LIMESTONE	651.20	-			
		0.4								0.4		TON	HAY MULCH	651.25	-			
		94								94		CY	TOPSOIL	651.35	-			
								80		80		SY	GRUBBING MATERIAL	651.40	-			
		1								1		LS	EPSC PLAN	652.10	-			
		40						40		80		HR	MONITORING EPSC PLAN	652.20	-			
		0.5						0.5		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
								100		100		SY	TEMPORARY EROSION MATTING	653.20	-			
		300						300		600		LF	PROJECT DEMARCATION FENCE	653.55	-			
				1						1		LS	TIMBER PAINTING, ENVIRONMENTAL PROTECTION	660.10	-			
				1						1		LS	TIMBER PAINTING, FIRE RETARDANT	660.20	-			
				1						1		LS	TIMBER PAINTING, INSECTICIDE/FUNGICIDE	660.30	-			
				535						535		SY	METAL ROOFING	661.10	-			
104										104		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
224										224		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
2										2		EACH	REMOVING SIGNS	675.50	-			
				12						12		EACH	SPECIAL PROVISION (BEARING DEVICE ASSEMBLY, COVERED BRIDGE)	900.620	-			
				8						8		EACH	SPECIAL PROVISION (TIMBER ARCH BEARING CONNECTION)	900.620	-			
				20						20		EACH	SPECIAL PROVISION (WOOD EPOXY REPAIRS)	900.620	-			
					1					1		LS	SPECIAL PROVISION (INCORPORATING SALVAGED BRIDGE COMPONENTS)	900.645	-			
				1						1		LS	SPECIAL PROVISION (LIGHTING FOR COVERED BRIDGE)	900.645	-			
				0.5	0.5					1		LS	SPECIAL PROVISION (REHABILITATING COVERED BRIDGE SUPERSTRUCTURE)	900.645	-			
				1						1		LS	SPECIAL PROVISION (REPAIRING STONE MASONRY, JAHN PERMEABLE MORTAR SYSTEM) (EAST ABUTMENT)	900.645	-			
				1						1		LS	SPECIAL PROVISION (REPAIRING STONE MASONRY, JAHN PERMEABLE MORTAR SYSTEM) (PIER)	900.645	-			
				1						1		LS	SPECIAL PROVISION (STONE MASONRY REPAIR MATERIAL, JAHN PERMEABLE MORTAR SYSTEM)	900.645	-			
1										1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650	-			
1										1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650	-			

PROJECT NAME: WOODSTOCK WOODSTOCK  
PROJECT NUMBER: BHO 1444(52) ST 1444(58)

FILE NAME: z96j262quant.dgn  
PROJECT LEADER: M. Sargent  
DESIGNED BY: S. Delia  
QUANTITY SHEET \*2

PLOT DATE: 23-JUL-2012  
DRAWN BY: P. Dustin  
CHECKED BY: R. Joy  
SHEET 6 OF 68

