

BRIDGE QUANTITY SHEET 2

SUMMARY OF BRIDGE QUANTITIES										TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES				
							SUPERSTRUCTURE	ABUTMENT NO. 1	PIER	ABUTMENT NO. 2	BRIDGE TOTAL		UNIT	ITEMS	ITEM NUMBER		QUANTITIES	UNIT	ITEMS
										1	1		LS	COFFERDAM (EAST ABUTMENT)	208.40				
									1		1		LS	COFFERDAM (PIER)	208.40				
									24		24		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
							0.5				0.5		LS	SHORING SUPERSTRUCTURE	502.10				
							1				1		LS	STRUCTURAL STEEL	506.75				
									3120		3120		LB	REINFORCING STEEL, LEVEL I	507.11				
									40		40		LF	DRILLING AND GROUTING DOWELS	507.16				
									5		5		GAL	WATER REPELLENT, SILANE	514.10				
							23.5				23.5		MFBM	STRUCTURAL LUMBER AND TIMBER, UNTREATED	522.20				
							37.38				37.38		MFBM	STRUCTURAL LUMBER AND TIMBER, TREATED	522.25				
							8.92				8.92		MFBM	NONSTRUCTURAL LUMBER, UNTREATED	522.30				
							1				1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
							1				1		LS	TIMBER PAINTING, ENVIRONMENTAL PROTECTION	660.10				
							1				1		LS	TIMBER PAINTING, FIRE RETARDANT	660.20				
							1				1		LS	TIMBER PAINTING, INSECTICIDE/FUNGICIDE	660.30				
							535				535		SY	METAL ROOFING	661.10				
								4	4	4	12		EACH	SPECIAL PROVISION (BEARING DEVICE ASSEMBLY, COVERED BRIDGE)	900.620				
									4	4	8		EACH	SPECIAL PROVISION (TIMBER ARCH BEARING CONNECTION)	900.620				
							20				20		EACH	SPECIAL PROVISION (WOOD EPOXY REPAIRS)	900.620				
							1				1		LS	SPECIAL PROVISION (LIGHTING FOR COVERED BRIDGE)	900.645				
							0.5				0.5		LS	SPECIAL PROVISION (REHABILITATING COVERED BRIDGE SUPERSTRUCTURE)	900.645				
										1	1		LS	SPECIAL PROVISION (REPAIRING STONE MASONRY, JAHN PERMEABLE MORTAR SYSTEM) (EAST ABUTMENT)	900.645				
									1		1		LS	SPECIAL PROVISION (REPAIRING STONE MASONRY, JAHN PERMEABLE MORTAR SYSTEM) (PIER)	900.645				
									0.5	0.5	1		LS	SPECIAL PROVISION (STONE MASONRY REPAIR MATERIAL, JAHN PERMEABLE MORTAR SYSTEM)	900.645				
									0.5	0.5	1		LU	SPECIAL PROVISION (ON-SITE MASONRY MOCK-UP AND TRAINING, JAHN PERMEABLE MORTAR SYSTEM N.A.B.I.)	900.650				

PROJECT NAME: WOODSTOCK WOODSTOCK
PROJECT NUMBER: BHO 1444(52) ST 1444(58)

FILE NAME: z96j262quant.dgn
PROJECT LEADER: M. Sargent
DESIGNED BY: S. Delia
BRIDGE QUANTITY SHEET *2

PLOT DATE: 23-JUL-2012
DRAWN BY: P. Dustin
CHECKED BY: R. Joy
SHEET 6C OF 68

