

# QUANTITY SHEET 2



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							23.2				23.2		M	REMOVE AND RESET GUARDRAIL	621.75				
							23				23		M	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							100				100		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							600				600		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
							1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL	641.10				
							236				236		M	100 MM YELLOW LINE	646.21				
							6				6		M	600 MM STOP BAR	646.26				
							4				4		EACH	LETTER OR SYMBOL	646.30				
							100				100		EACH	LINE STRIPING TARGETS	646.76				
									330		330		SM	GEOTEXTILE UNDER STONE FILL	649.31				
							10				10		SM	GEOTEXTILE FOR SILT FENCE	649.51				
							100				100		SM	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							130				130		SM	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							10				10		KG	SEED	651.15				
							10				10		KG	SEED, WINTER RYE	651.17				
							100				100		KG	FERTILIZER	651.18				
							1				1		T	AGRICULTURAL LIMESTONE	651.20				
							1				1		T	HAYMULCH	651.25				
							10				10		CM	TOPSOIL	651.35				
									160		160		SM	GRUBBING MATERIAL	651.40				
							1				1		LS	EPSC PLAN	652.10				
							100				100		HR	MONITORING EPSC PLAN	652.20				
							1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							150				150		SM	TEMPORARY EROSION MATTING	653.20				
							30				30		CM	VEHICLE TRACKING PAD	653.35				
								91			91		M	BARRIER FENCE	653.50				
							2.4				2.4		SM	TRAFFIC SIGNS, TYPE A	675.20				
							36				36		M	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							5				5		EACH	REMOVING SIGNS	675.50				
							2				2		EACH	ERECTING SALVAGED SIGNS	675.60				
							42				42		M	SPECIAL PROVISION (ALUMINUM APPROACH RAILING, ANODIZED)	900.640				
									27		27		M	SPECIAL PROVISION (BRIDGE RAILING, ANODIZED 3 RAIL ALUMINUM)	900.640				
									27		27		M	SPECIAL PROVISION (BRIDGE RAILING, ANODIZED ALUMINUM/PEDESTRIAN)	900.640				
							1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
							1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650				