

QUANTITY SHEET

| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | | | | | TOTALS | | | DESCRIPTIONS | | DETAILED SUMMARY OF QUANTITIES | | |
|---------------------------------|----------|---------|-----------------|---------|------|-------------|-------------|-----------------|-----------------|-------|-------------|-------|--------|--|-------------|--------------|------|---|--|--|
| FULL E & C | TRAINING | ROADWAY | EROSION CONTROL | CHANNEL | PIER | ABUT. NO. 2 | ABUT. NO. 1 | SUPER STRUCTURE | BRIDGE QUANTITY | ROUND | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | QUANTITIES | UNIT | ITEMS | | |
| | | 1 | | | | | | | | | 1 | | LS | CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS | 201.10 | | | | | |
| | | 350 | | | | | | | | | 350 | | CY | COMMON EXCAVATION | 203.15 | | | TEMPORARY EROSION CONTROL ITEMS (INCLUDED IN EROSION CONTROL ITEMS) | | |
| | | 10 | | 80 | | | | | 80 | | 90 | | CY | UNCLASSIFIED CHANNEL EXCAVATION | 203.27 | 10 | CY | 204.20 TRENCH EXCAVATION OF EARTH | | |
| | | | 10 | | | | | | | | 10 | | CY | TRENCH EXCAVATION OF EARTH | 204.20 | 10 | CY | 301.15 SUBBASE OF GRAVEL | | |
| | | | | | | 30 | 30 | | 60 | | 60 | | CY | STRUCTURE EXCAVATION | 204.25 | 5 | HR | 608.25 ALL PURPOSE EXCAVATOR RENTAL, TYPE I | | |
| | | | | | | 20 | 20 | | 40 | | 40 | | CY | GRANULAR BACKFILL FOR STRUCTURES | 204.30 | 10 | CY | 613.10 STONE FILL, TYPE I | | |
| | | 190 | | | | | | | | | 190 | | SY | COLD PLANING, BITUMINOUS PAVEMENT | 210.10 | 130 | SY | 649.51 GEOTEXTILE FOR SILT FENCE | | |
| | | 450 | 10 | | | | | | | | 460 | | CY | SUBBASE OF GRAVEL | 301.15 | 10 | LB | 651.17 SEED, WINTER RYE* | | |
| | | 0.7 | | | | | | | | | 1 | | CWT | EMULSIFIED ASPHALT | 404.65 | 10 | EACH | 653.15 HAY BALES | | |
| | | 100 | | | | | | | | | 100 | | TON | BITUMINOUS CONCRETE PAVEMENT (PG 58-28) | 406.25 | 140 | SY | 653.20 TEMPORARY EROSION MATTING | | |
| | | | | | | 29 | 22 | | 51 | | 51 | | CY | CONCRETE, HIGH PERFORMANCE CLASS B | 501.34 | 30 | CY | 653.35 VEHICLE TRACKING PAD | | |
| | | | | | | | | 1 | 1 | | 1 | | LS | SHORING SUPERSTRUCTURE | 502.10 | | | * 50/50 MIX OF ANNUAL RYEGRASS (LOLIUM MUTILFLORUM) AND CEREAL (WINTER) RYE | | |
| | | | | | | | | 630 | 630 | | 630 | | LB | STRUCTURAL STEEL | 506.60 | | | | | |
| | | | | | | 4450 | 3660 | | 8110 | | 8110 | | LB | REINFORCING STEEL | 507.15 | | | EARTHWORKS SUMMARY | | |
| | | | | | | | | 15.1 | 15.1 | | 15 | | MFBM | STRUCTURAL LUMBER AND TIMBER, UNTREATED | 522.20 | | | FILL AVAILABLE: | | |
| | | | | | | | | 6.5 | 6.5 | | 7 | | MFBM | STRUCTURAL LUMBER AND TIMBER, TREATED | 522.25 | 350 | CY | COMMON EXCAVATION: 350 X 1.0 | | |
| | | | | | | | | 11.3 | 11.3 | | 11 | | MFBM | NONSTRUCTURAL LUMBER, UNTREATED | 522.30 | 54 | CY | UNCLASSIFIED CHANNEL EXCAVATION: 90 X 0.6 | | |
| | | | | | | | | 1.3 | 1.3 | | 1 | | MFBM | NONSTRUCTURAL LUMBER, TREATED | 522.35 | 6 | CY | TRENCH EXCAVATION OF EARTH: 10 X 0.6 | | |
| | | | | | | | | 1 | 1 | | 1 | | LS | STRUCTURAL GLUED LAMINATED TIMBER (11.4 MBFM) (DECK PANELS) | 522.40 | 36 | CY | STRUCTURE EXCAVATION: 60 X 0.6 | | |
| | | | | | | | | 1 | 1 | | 1 | | LS | STRUCTURAL GLUED LAMINATED TIMBER (7.6 MBFM) (FLOORBEAMS) | 522.40 | 446 | CY | SUBTOTAL | | |
| | | | | | | 0.5 | 0.5 | | 1 | | 1 | | EACH | PARTIAL REMOVAL OF STRUCTURE | 529.20 | 4 | CY | ROUNDING | | |
| | | | | 20 | | | | | 20 | | 20 | | HR | DRAGLINE RENTAL, TYPE I | 608.20 | 450 | CY | TOTAL | | |
| | | | 5 | | | | | | | | 5 | | HR | ALL PURPOSE EXCAVATOR RENTAL, TYPE I | 608.25 | 450 | CY | FILL AVAILABLE | | |
| | | 40 | 10 | | | | | | | | 50 | | CY | STONE FILL, TYPE I | 613.10 | 30 | CY | FILL REQUIRED | | |
| | | | | 80 | | | | | 80 | | 80 | | CY | STONE FILL, TYPE II | 613.11 | 420 | CY | WASTE | | |
| | | 227 | | | | | | | | | 227 | | LF | STEEL BACKED TIMBER GUARDRAIL | 621.18 | | | | | |
| 1 | | | | | | | | | | | 1 | | LS | FIELD OFFICE, ENGINEERS | 631.10 | | | | | |
| 1 | | | | | | | | | | | 1 | | LS | TESTING EQUIPMENT, CONCRETE | 631.16 | | | N.A.B.I. = NOT A BID ITEM | | |
| 1 | | | | | | | | | | | 1 | | LU | FIELD OFFICE TELEPHONE (N.A.B.I.) | 631.25 | | | | | |
| | | | | | | | | | | | 1 | | HR | EMPLOYEE TRAINEESHIP | 634.10 | | | | | |
| | | | | | | | | | | | 1 | | LS | MOBILIZATION / DEMOBILIZATION | 635.11 | | | | | |
| | | | | | | | | | | | 1 | | LS | TRAFFIC CONTROL | 641.10 | | | | | |
| | | | | 230 | | | | | 230 | | 230 | | SY | GEOTEXTILE UNDER STONE FILL | 649.31 | | | | | |
| | | | 130 | | | | | | | | 130 | | SY | GEOTEXTILE FOR SILT FENCE | 649.51 | | | | | |
| | | | 10 | | | | | | | | 10 | | LB | SEED | 651.15 | | | | | |
| | | | 10 | | | | | | | | 10 | | LB | SEED, WINTER RYE | 651.17 | | | | | |
| | | | 80 | | | | | | | | 80 | | LB | FERTILIZER | 651.18 | | | | | |
| | | | 1 | | | | | | | | 1 | | TON | AGRICULTURAL LIMESTONE | 651.20 | | | | | |
| | | | 1 | | | | | | | | 1 | | TON | HAYMULCH | 651.25 | | | | | |
| | | | 10 | | | | | | | | 10 | | CY | TOPSOIL | 651.35 | | | | | |
| | | | | 220 | | | | | 220 | | 220 | | SY | GRUBBING MATERIAL | 651.40 | | | | | |

PROJECT NAME: SALISBURY - CORNWALL
 PROJECT NUMBER: BHO 1445(27)
 FILE NAME: 96j268\Structures\sj268qs.xls PLOT DATE: 4/25/2007
 PROJECT MANAGER: R. WHITCOMB DRAWN BY: G. ROY
 DESIGNED BY: C. CARLSON CHECKED: C. CARLSON
 QUANTITY SHEET #1 SHEET 5 OF 60

1
 ADDENDUM #1: REVISED APRIL 25, 2007