

QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES													DETAILED SUMMARY OF QUANTITIES		
FULL E&C	EROSION CONTROL	NON-FEDERAL PARTICIPATING	EMPLOYEE TRAINEE-SHIP	UTILITIES	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND	QUANTITIES	UNIT	ITEMS	
						7	7	EA	CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.10	-				
						1	1	EA	CONCRETE MANHOLE WITH CAST IRON COVER	604.11	-				
				4			4	EA	PRECAST REINFORCED CONC. MANHOLE WITH CAST IRON COVER (4 FT. DIA.)	604.21	-				
						5	5	EA	CHANGING ELEVATION OF DI'S, CB'S, OR MH'S	604.40	-				
						5	5	EA	CHANGING ELEVATION OF SEWER MANHOLE	604.42	-				
						4	4	EA	CAST IRON GRATE WITH FRAME, TYPE D	604.47	-				
						1	1	EA	CAST IRON GRATE WITH FRAME, TYPE E	604.48	-				
						3	3	EA	CAST IRON COVER WITH FRAME	604.55	-				
				2		10	12	HR	POWER GRADER RENTAL	608.15	EST				
				2		10	12	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST				
				2		10	12	HR	POWER BROOM RENTAL	608.30	EST				
				2		10	12	HR	POWER BROOM RENTAL, TYPE II	608.31	EST				
				2		10	12	HR	TRUCK RENTAL	608.37	EST				
				2		10	12	HR	LOADER RENTAL, TYPE I	608.40	EST				
						1	1	T	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST				
						2	2	CM	STONE FILL TYPE I (MOD.)	613.10	-				
						354	355	M	VERTICAL GRANITE CURB	616.21	1				
					24		24	M	GRANITE BRIDGE CURB	616.22	-				
						7	7	M	CAST-IN-PLACE CEMENT CONCRETE CURB, TYPE B	616.28	-				
						180	184	M	REMOVAL OF EXISTING CURB	616.41	4				
						480	490	SM	PORTLAND CEMENT CONCRETE SIDEWALK, 125 mm	618.10	10				
						2	3	T	BITUMINOUS CONCRETE SIDEWALK	618.15	0.4				
						9	9	SM	DETECTABLE WARNING SURFACE	618.30	-				
						18	20	M	CHAIN LINK FENCE, 1.2M	620.11	2				
						92	95	M	REMOVAL OF EXISTING FENCE	620.55	3				
						18	18	M	TEMPORARY TRAFFIC BARRIER	621.90	-				
						25	25	M	SLEEVES FOR UTILITIES (125 mm)	625.10	-				
						85	85	M	SLEEVES FOR UTILITIES (100 mm)	625.10	-				
						5	5	M	SLEEVES FOR UTILITIES (400 mm)	625.10	-				
						80	80	M	PVC SEWER PIPE (200 mm)	628.35	-				

PROJECT NAME :	PROJECT NO. :
WATERBURY	BRO 1446(26)
DESIGN FILE NAME: ...05-QUANTITY2.ptf	PLOT DATE: 01/27/2004
IPARM FILE NAME:	SURVEY DATE: 1996
SURVEYED BY: VTrans	DRAWN BY: M. MEILLEUR
SQUAD LEADER: R. GINGRAS	SHEET: 5 OF 63
QUANTITY SHEET #2	

...:\05-QUANTITY2.BIT 01/27/2004 03:26:25 PM