

STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SUMMARY SHEET



STATION		POS.	301.35	604.42	616.21	616.28	616.41	618.10	618.15	620.55	629.20											REMARKS
BEGIN	END		SUBBASE OF DENSE GRADED CRUSHED STONE CM	CHANGING ELEV. OF SEWER MANHOLE EA	VERTICAL GRANITE CURB M	CAST-IN-PLACE CEMENT CONCRETE CURB, TYPE B	REMOVAL OF EXISTING CURB M	P.C. CONCRETE SIDEWALK, 125 mm SM	BITUMINOUS CONCRETE SIDEWALK T	REMOVAL OF EXISTING FENCE M	ADJUST ELEV VALVE BOX EA											
BIDWELL LANE																						
B 1+005.4	B 1+015.8	LT&RT	28.6																			
B 1+010.0	B 1+015.0	LT	0.6					1.3														
B 1+014.3	1+094.4	LT-RT			10.3																	
B 1+015.8		LT				6	6															
B 1+017.3	1+099.3	LT-RT					15															
UNION STREET																						
U 10+004.5	U 10+034.0	LT&RT	137.7																			
U 10+009.0		LT								1												
U 10+036.0	1+175.4	RT-LT	35.5					50									CONSTRUCT SIDEWALK RAMP, TYPE VI AT STA. 1+170.6, LT.					
U 10+062.0	1+175.4	RT-LT			56		60															
RELOCATED RAILROAD STREET																						
R 5+005.0	R 5+071.0	LT&RT	286.7																			
R 5+033.0		RT								1												
R 5+064.2	R 5+068.0	LT							3.8													
R 5+073.0		LT		1																		
R 5+077.0	1+175.3	LT-RT	35.1		76		94										CONSTRUCT SIDEWALK RAMP, TYPE VI AT STA. 1+169.1, RT.					
SUBTOTALS			524.2	1	142.3	6	81	144	1.3	3.8	2											
SHEET 9 SUBTOTALS			497.0	4	211.7	-	99	336	1.3	87.7	6											
SHEET 10 SUBTOTALS			524.2	1	142.3	6	81	144	1.3	3.8	2											
SUBTOTALS			1021.2	5	354	6	180	480	2.6	91.5	8											
ROUNDING			8.8	-	6	1	4	10	0.4	3.5	-											
PROJECT TOTALS			1030	5	360	7	184	490	3	95	8											

PROJECT NAME : WATERBURY	PROJECT NO. : BRO 1446(26)
DESIGN FILE NAME: ...10-Item detail2.ptf	PLOT DATE: 01/26/2004
IPARM FILE NAME:	SURVEY DATE: 06/07/00
SURVEYED BY: VTrans	DRAWN BY: M. MEILLEUR
DESIGNED BY: R. GINGRAS	SHEET: 10 OF 63
ITEM DETAIL SUMMARY SHEET #2	

...D:\011165\10-Item detail2.rtf 01/26/2004 08:28:38 AM