



TRAFFIC CONTROL PLAN
N.T.S.

- NOTES:**
1. ALL TRAFFIC SIGN PLACEMENT AND SPACING SHALL CONFORM TO THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) 2000 EDITION.
 2. "BRIDGE CLOSED" SIGNS SHALL BE MOUNTED AND MAINTAINED ON LIGHTED TYPE III BARRICADES.
 3. TEMPORARY TRAFFIC BARRIERS SHALL BE PLACED SO AS TO PHYSICALLY EXCLUDE TRAFFIC FROM THE ENTIRE ROADWAY WIDTH OR AT THE DISCRETION OF THE ENGINEER.
 4. ALL SIGNS SHOWN ON THIS SHEET SHALL BE MANUFACTURED USING THE MATERIALS, COLORS AND REFLECTORIZATION AS DESCRIBED ON VTrans STANDARD E-100M.
 5. "BRIDGE CLOSED" SIGN PLACEMENT MAY CHANGE WITH FIELD CONDITIONS OR AT THE DISCRETION OF THE ENGINEER.
 6. ALL COSTS OF INSTALLING, MAINTAINING, AND REMOVING THE SIGNS AND BARRICADES IN THIS TRAFFIC CONTROL PLAN AS NECESSARY TO MEET PROJECT CONDITIONS WILL BE SUBSIDIARY TO TRAFFIC CONTROL, ITEM 64110.
 7. REFER TO VTrans STANDARD E-100M FOR CONSTRUCTION APPROACH SIGNING ON U.S. ROUTE 2, VT ROUTE 100, BIDWELL LANE, RAILROAD STREET, UNION STREET, AND STOWE STREET.
 8. AT THE NORTHERLY END OF STOWE STREET AT THE VT ROUTE 100 INTERSECTION, INSTALL A *SIGN FOR TRAFFIC TURNING ONTO STOWE STREET.

PLAN REF. SYMBOL	ID NUMBER	SIGN TEXT	SIZE OF SIGN		NUMBER OF SIGNS REQ'D.	POST SIZE AND NUMBER REQ'D., EACH SIGN	TOTAL AREA (SM)	REMARKS
			WIDTH	HEIGHT				
①	---	DRY BRIDGE CLOSED ON STOWE ST.	1800	1200	4	TWO 4.6 M LONG 4.5 KG/M FLANGED CHANNEL STEEL POSTS.	8.64	SEE NOTES 4 & 8
②	---	RT. 2 AND RT. 100 TRAFFIC NOT AFFECTED	3000	900	2	TWO 4.6 M LONG 4.5 KG/M FLANGED CHANNEL STEEL POSTS.	5.40	SEE NOTE 4
③	---	LOCAL TRAFFIC SEEK ALT. ROUTE	2400	900	2	TWO 4.6 M LONG 4.5 KG/M FLANGED CHANNEL STEEL POSTS.	4.32	SEE NOTE 4
④	W20-2	DETOUR AHEAD	1200	1200	7	TWO 4.6 M LONG 4.5 KG/M FLANGED CHANNEL STEEL POSTS.	7.20	SEE VTrans STANDARD E-102M
⑤	M4-9V	STOWE ST. DETOUR	750	750	5	ONE 4.6 M LONG 4.5 KG/M FLANGED CHANNEL STEEL POST.	2.81	---
⑥	M4-9R	STOWE ST. DETOUR	750	750	4	ONE 4.6 M LONG 4.5 KG/M FLANGED CHANNEL STEEL POST.	2.25	---
⑦	M4-9L	STOWE ST. DETOUR	750	750	3	ONE 4.6 M LONG 4.5 KG/M FLANGED CHANNEL STEEL POST.	1.69	---
⑧	R11-2	BRIDGE CLOSED	1200	750	2	---	1.80	SEE NOTES 2 & 3
⑨	M4-8a	END DETOUR	600	450	3	ONE 4.6 M LONG 4.5 KG/M FLANGED CHANNEL STEEL POST.	0.81	---

NOTE:
ALL DIMENSIONS IN MILLIMETERS EXCEPT WHERE OTHERWISE INDICATED



PROJECT NAME: WATERBURY
 PROJECT NUMBER: BRO 1446(26)
 FILE NAME: ...29-traffic control.ptf PLOT DATE: 01/26/2004
 PROJECT LEADER: G EDWARDS/R GINGRAS DRAWN BY: S BURBANK
 DESIGNED BY: R GINGRAS CHECKED BY: R GINGRAS
TRAFFIC CONTROL PLAN SHEET 29 OF 63

...29-traffic control.ptf 01/26/2004 08:18:25 AM