

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	EROSION CONTROL	BRIDGE	WATER MAIN (PARTICIPATING)	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1					1		LS	CLEARING AND GRUBBING (INCLUDING INDIVIDUAL TREES AND STUMPS)	201.10				
					142					142		CY	COMMON EXCAVATION	203.15				
							70			70		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
					10					10		CY	EARTH BORROW	203.30				
								15		15		CY	SAND BORROW	203.31				
						10		40		50		CY	TRENCH EXCAVATION OF EARTH	204.20				
							490	15		505		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
							750			750		CY	COFFERDAM EXCAVATION, EARTH	208.30				
							460			460		CY	COFFERDAM EXCAVATION, ROCK	208.35				
							1			1		LS	COFFERDAM (ABUTMENT #1)	208.40				
							1			1		LS	COFFERDAM (ABUTMENT #2)	208.40				
					170					170		SY	COLD PLANING-BIT. PAVEMENT	210.10				
					190					190		CY	SUBBASE OF GRAVEL	301.15				
					2					2		CWT	EMULSIFIED ASPHALT	404.65				
					93					93		TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.25				
							296			296		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
							3260			3260		LB	STRUCTURAL STEEL (ROLLED BEAM)	506.50				
							2730			2730		LB	STRUCTURAL STEEL	506.60				
							35090			35090		LB	REINFORCING STEEL	507.15				
							124	35		159		LF	DRILLING AND GROUTING DOWELS	507.16				
							4920			4920		LB	EPOXY COATED REINFORCING STEEL	507.17				
							1			1		LS	STRUCTURAL PAINTING, SHOP APPLIED (2 TONS)	513.25				
							1			1		LS	STRUCTURAL PAINTING, FIELD APPLIED (23 TONS)	513.30				
							1			1		LS	CONTAINMENT & ENVIRONMENTAL PROTECTION, SHOP	513.35				
							1			1		LS	CONTAINMENT & ENVIRONMENTAL PROTECTION, FIELD	513.36				
							1			1		LS	SURFACE PREPARATION, SHOP (2 TONS)	513.40				
							1			1		LS	SURFACE PREPARATION, FIELD (23 TONS)	513.41				
							10			10		GAL	WATER REPELLENT (MOD. - SILANE)	514.10				
							16			16		LF	BRIDGE EXPANSION JOINT (ASPHALT PLUG) (MOD.)	516.10				
							1.23			1.23		MFBM	NON - STRUCTURAL LUMBER-TREATED	522.35				
							193			193		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
							1			1		EACH	REMOVAL OF STRUCTURE (1680 SF - EST.)	529.15				
							1			1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
							14			14		EACH	BEARING DEVICE ASSEMBLY (FABRIC)	531.10				
							193			193		SY	CONCRETE CLASS AA OVERLAY (MOD. - FIBER REINFORCED POLYMER DECK)	580.19				
						10				10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
					1					1		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
					5		1			6		CY	STONE FILL, TYPE I	613.10				
						10				10		CY	STONE FILL, TYPE I (MOD. - CHECK DAM)	613.10				
						16				16		CY	STONE FILL, TYPE I (MOD. - CONSTRUCTION ENTRANCE)	613.10				

PROJECT NAME: **BRADFORD**
 PROJECT NUMBER: **STP 1447(28)**
 FILE NAME: s96j286.xls.dgn
 PROJECT MANAGER: C.P.WILLIAMS
 DESIGNED BY: M.GAGULIC
 QUANTITY SHEET #1
 PLOT DATE: 11/02/2006
 DRAWN BY: M.FESSEL
 CHECKED BY: R.S.YOUNG
 SHEET 3 OF 63