

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	EROSION CONTROL	BRIDGE	WATER MAIN (PARTICIPATING)	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							130			130		CY	STONE FILL, TYPE III	613.12				
						410				410		LF	SNOW FENCE (MOD. - PDF)	620.70				
					243					243		LF	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED) (MOD. - 8' POSTS)	621.21				
					4					4		EACH	TERMINAL CONNECTOR FOR STEEL BEAM GUARD RAIL	621.53				
					4					4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
					180					180		LF	REMOVL AND DISP OF GUARD RAIL	621.80				
					60					60		LF	TEMPORARY TRAFFIC BARRIER	621.90				
								70		70		LF	DUCTILE, IRON PIPE, CEM LINED (8")	629.24				
								2		2		EACH	GATE VALVE WITH VALVE BOX (8")	629.27				
								1		1		LS	TRANSFER TO NEW SYSTEM-WATER SYSTEM	629.42				
								1		1		LS	WATER MAIN ON BRIDGE (8")	629.60				
									1	1		LS	FIELD OFFICE-ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT - CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17				
									1	1		LS	TESTING EQUIPMENT - PROTECTIVE COATINGS	631.18				
									1	1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25				
					1					1		LS	MOBILIZATION / DEMOBILIZATION	635.11				
					1					1		LS	TRAFFIC CONTROL	641.10				
					15	10	150			175		SY	GEOTEXTILE UNDER STONE FILL	649.31				
						90				90		SY	GEOTEXTILE FOR SILT FENCE	649.51				
						90				90		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
						10				10		LB	SEED	651.15				
						10				10		LB	SEED-WINTER RYE	651.17				
						100				100		LB	FERTILIZER	651.18				
						1				1		TON	AGRICULTURAL LIMESTONE	651.20				
						1				1		TON	HAYMULCH	651.25				
						10				10		EACH	HAY BALES FOR EROSION CONTROL	651.26				
						80				80		SY	GRUBBING MATERIAL	651.40				
						1				1		LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10				
						40				40		HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20				
						1				1		LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30				
						110				110		SY	EROSION MATTING	654.10				
					20					20		SF	TRAFFIC SIGNS, TYPE A	675.20				
					68					68		LF	FLANGED CHANNEL SIGN POST	675.301				
					7					7		EACH	REMOVING SIGNS	675.50				
					3					3		EACH	ERECTING SALVAGED SIGNS	675.60				

PROJECT NAME: **BRADFORD**  
 PROJECT NUMBER: **STP 1447(28)**  
 FILE NAME: s96j286xls.dgn PLOT DATE: 11/02/2006  
 PROJECT MANAGER: C.P.WILLIAMS DRAWN BY: M.FESSEL  
 DESIGNED BY: M.GAGULIC CHECKED BY: R.S.YOUNG  
 QUANTITY SHEET #2 SHEET 4 OF 63