STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES																TOTALS				DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
FULL C.E. ITEMS	EROSION CONTROL	ROADWAY	CHANNEL	ABUTMENT NO.1	ABUTMENT NO.2	WINGWALL NO.1	WINGWALL NO.2	WINGWALL NO.3	WINGWALL NO.4	WINGWALL NO.3A	WINGWALL NO.4A	SUPER-STRUCTURE	ALTERNATE A	ALTERNATE B	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
		1															1		LS	TRAFFIC CONTROL	641.10			
		73	67												67	7	140		SY	GEOTEXTILE UNDER STONE FILL	649.31			
	160															9	160		SY	GEOTEXTILE FOR SILT FENCE	649.51			
	10															5	10		LB	SEED	651.15			
	50															9	50		LB	FERTILIZER	651.18			
	1															0.8	1		TON	AGRICULTURAL LIMESTONE	651.20			
	1															0.8	1		TON	HAY MULCH	651.25			
	80															5	80		CY	TOPSOIL	651.35			
	1																1		LS	EPSC PLAN	652.10			
	95																95		HR	MONITORING EPSC PLAN	652.20			
	1																1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30			
	320															2	320		SY	TEMPORARY EROSION MATTING	653.20			
	10																10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25			
		110															110		LF	BARRIER FENCE	653.50			
		450															450		LF	PROJECT DEMARCATION FENCE	653.55			
		2															2		EACH	DECIDUOUS SEEDLINGS (ACER RUBRUM) (3 GAL. CONT.) (6'-8')	656.16			
		2															2		EACH	DECIDUOUS SEEDLINGS (ACER SACCHARUM) (3 GAL. CONT.) (6'-8')	656.16			
		2															2		EACH	DECIDUOUS SEEDLINGS (QUERCUS RUBRA) (3 GAL. CONT.) (6'-8')	656.16			
		3															3		EACH	EVERGREEN TREES (PINUS STROBUS) (1 GAL. CONT.) (3'-4')	656.20			
		28.75															28.75		SF	TRAFFIC SIGNS, TYPE A	675.20			
		52															52		LF	FLANGED CHANNEL SIGN POST	675.301			
				50											50	4	50		CY	SPECIAL PROVISION (REBUILT STONE MASONRY)	900.608			
												8			8		8		EACH	SPECIAL PROVISION (BEARING DEVICE ASSEMBLY, COVERED BRIDGE)	900.620			
												57			57		57		EACH	SPECIAL PROVISION (WOOD EPOXY REPAIRS)	900.620			
				2.7	7.0	0.5	0.7	1.4	2.3	0.2	0.2				15	0.5	15		GAL	SPECIAL PROVISION (CONCRETE STAINING AND SEALING)	900.625			
		228.5															228.5		LF	SPECIAL PROVISION (HD STEEL BEAM GUARDRAIL, WEATHERING) (WOOD POSTS)	900.640			
		1															1		LS	SPECIAL PROVISION (REMOVE AND RESET EXISTING STONE WALL)	900.645			
												1			1		1		LS	SPECIAL PROVISION (TIMBER PAINTING, ENVIRONMENTAL PROTECTION)	900.645			
												1			1		1		LS	SPECIAL PROVISION (TIMBER PAINTING, FIRE RETARDANT)	900.645			
												1			1		1		LS	SPECIAL PROVISION (TIMBER PAINTING, INSECTICIDE/FUNGICIDE)	900.645			
		700															700		SF	SPECIAL PROVISION (TEMPORARY RETAINING WALL)	900.670			
																				BEGIN ALTERNATE ITEMS				
																				ALTERNATE A (IN-PLACE REHABILITATION)				
													1		1		1		LS	SHORING SUPERSTRUCTURE	502.10			
													1		1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20			
													1		1		1		LS	SPECIAL PROVISION (REHABILITATING COVERED BRIDGE SUPERSTRUCTURE)	900.645			
																				ALTERNATE B (RELOCATED REHABILITATION)				
														1	1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20			
														1	1		1		LS	SPECIAL PROVISION (HANDLING, TRANSPORT, AND RE-ERECTION OF COVERED BRIDGE SUPERSTRUCTURE)	900.645			
														1	1		1		LS	SPECIAL PROVISION (REHABILITATING COVERED BRIDGE SUPERSTRUCTURE)	900.645			
																				END ALTERNATE ITEMS				

Hoyle, Tanner & Associates, Inc.

PROJECT NAME: **MONTGOMERY**
PROJECT NUMBER: **BHO 1448(23)**

FILE NAME: **Z96J302quant.xls**
PROJECT MANAGER: **J.H.WEAVER**
DESIGNED BY: **J.BICJA**
QUANTITY SHEET (2 OF 2)

PLOT DATE: **7/25/2008**
DRAWN BY: **J.BICJA**
CHECKED BY: **S.T.JAMES**
SHEET **6** OF **54**