

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES				
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							290				290		CY	COMMON EXCAVATION	203.15				
							150				150		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									30		30		CY	STRUCTURE EXCAVATION	204.25				
									30		30		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
									1		1		LS	COFFERDAM (SLEEPER SLAB #1)	208.40				
							200				200		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25				
							70				70		CY	AGGREGATE SURFACE COURSE	401.10				
									4		4		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
									400		400		LB	REINFORCING STEEL, LEVEL I	507.11				
									102		102		LF	PRESTRESSED CONCRETE VOIDED SLABS (21 1/2" - 22" X 48")	510.22				
									102		102		LF	PRESTRESSED CONCRETE VOIDED SLABS (21" - 21 1/2" X 48")	510.22				
									153		153		LF	GROUTING SHEAR KEYS	510.24				
									25		25		GAL	WATER REPELLENT, SILANE	514.10				
									119		119		LF	BRIDGE RAILING, GALVANIZED HDSB/FASCIA MOUNTED/STEEL TUBING	525.44				
							1				1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
									16		16		EACH	BEARING DEVICE ASSEMBLY, STEEL REINFORCED ELASTOMERIC PAD	531.17				
									1		1		LS	PRECAST CONCRETE STRUCTURE (SLEEPER SLAB #1)	540.10				
									1		1		LS	PRECAST CONCRETE STRUCTURE (SLEEPER SLAB #2)	540.10				
								10			10		CY	STONE FILL, TYPE I	613.10				
							20				20		CY	STONE FILL, TYPE II	613.11				
									420		420		CY	STONE FILL, TYPE IV	613.13				
							120				120		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215				
							4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
							2				2		EACH	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM W/ 8FT POSTS	621.738				
							100				100		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
							190				190		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								40			40		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								90			90		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								10			10		LB	SEED	651.15				
								20			20		LB	FERTILIZER	651.18				
								0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20				
								0.5			0.5		TON	HAY MULCH	651.25				
							90				90		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								10			10		HR	MONITORING EPSC PLAN	652.20				

PROJECT NAME: MONTGOMERY
 PROJECT NUMBER: BHO 1448(27)
 FILE NAME: s96j306qs.dgn
 PROJECT LEADER: C. CARLSON
 DESIGNED BY: H. SALLS
 QUANTITY SHEET 1
 PLOT DATE: 21-NOV-2013
 DRAWN BY: R. PELLET
 CHECKED BY: H. SALLS
 SHEET 5 OF 30