

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	EROSION CONTROL	UTILITIES	TRAINING	BRIDGE	FULL E&C	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				110				610		720		CY	STONE FILL, TYPE IV	613.13				
				335						335		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28				
				195						195		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10				N.A.B.I. = NOT A BID ITEM
				24						24		SF	DETECTABLE WARNING SURFACE	618.30				FPQ = FINAL PAY QUANTITY
				685						685		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						300				300		LF	DUCTILE IRON PIPE, CEMENT-LINED (12")	629.24				
						3				3		LF	DUCTILE IRON PIPE, CEMENT-LINED (14")	629.24				
						45				45		LF	DUCTILE IRON PIPE, CEMENT-LINED (8")	629.24				
						1				1		EACH	GATE VALVE WITH VALVE BOX (12")	629.27				
						2				2		EACH	GATE VALVE WITH VALVE BOX (6")	629.27				
						1				1		EACH	HYDRANT	629.28				
						1				1		LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM	629.42				
						135				135		TON	CRUSHED STONE BEDDING	629.54				
				300						300		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
				2000						2000		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1400			1400		HR	EMPLOYEE TRAINEESHIP	634.10				
				1						1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
				1						1		LS	TRAFFIC CONTROL	641.10				
				1						1		LS	PUBLIC RELATIONS OFFICER	641.12				
				1450						1450		LF	4 INCH WHITE LINE	646.20				
				1450						1450		LF	4 INCH YELLOW LINE	646.21				
				28						28		LF	CROSSWALK MARKING	646.31				
				20				530		550		SY	GEOTEXTILE UNDER STONE FILL	649.31				
					190					190		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
					380					380		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
					10					10		LB	SEED	651.15				
					10					10		LB	SEED, WINTER RYE	651.17				
					30					30		LB	FERTILIZER	651.18				
					1					1		TON	AGRICULTURAL LIMESTONE	651.20				
					0.1					0.1		TON	HAY MULCH	651.25				
				40						40		CY	TOPSOIL	651.35				
								170		170		SY	GRUBBING MATERIAL	651.40				
					1					1		LS	EPSC PLAN	652.10				
					100					100		HR	MONITORING EPSC PLAN	652.20				
					1					1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
					160					160		SY	TEMPORARY EROSION MATTING	653.20				

PROJECT NAME: **NEWPORT CITY**  
PROJECT NUMBER: **BRO 1449(25)**  
FILE NAME: e96j314\_qs.xls PLOT DATE: 11/22/2011  
PROJECT LEADER: C. CARLSON DRAWN BY: STR3  
DESIGNED BY: D. PETERSON CHECKED BY: D. PETERSON  
QUANTITY SHEET #2 SHEET 5 OF 75