



Item 203.15, Common Excavation

Station	Dist	Area	Volume
(Butt) 11+00	50	20.77	2525.5
11+50	465	80.25	2563.0
		81.75	5173.8
(Butt) 11+96.5		142.28	5208.7
		E. 13c	
(Butt) 14+97.5	2.5	97.25	314.7
15+00	50	154.54	9424.5
15+50	50	222.44	10676.3
16+00	37.5	204.61	7672.9
16+37.5	12.5	204.61	2296.4
		162.81	2316.7
16+50	50	166.06	5836.0
			5917.3
17+00	25	70.63	1277.3
		31.55	1292.9
17+25	25	32.81	628.9
			644.5
17+50	6.5	18.76	159.5
(Butt) 17+58.5		18.76	159.5
		45935.8	1703.2 cy
		46144.0	= 1710.8 cy
Total			127

STA. 17+50 TO STA. 17+75

PROJECT NAME: NEWPORT CITY	PLOT DATE: 22-NOV-2011
PROJECT NUMBER: BRO 1449(25)	DRAWN BY: C. MOONEY
FILE NAME: 96J314/STR/96J314xsl.dgn	CHECKED BY: C. CARLSON
PROJECT LEADER: C. CARLSON	SHEET 56 OF 75
DESIGNED BY: D. PETERSON	
MAINLINE SECTION 8	