



BILL OF MATERIAL

SHIP	SHIP MARK	NO. PCS.	PIECE MARK	DESCRIPTION	LENGTH	REMARKS	WT.
1	2G4			BRIDGE GIRDER			
		1	wp2	PL 1/2 X 32	52'-11 1/8"		2888
		1	fp2	PL 2 1/2 X 18	52'-11 1/8"		7305
		1	fp2	PL 2 1/2 X 18	52'-11 1/8"		7305
		1	ps	SEE SHT. 26			
		2	ps	SEE SHT. 26			
		1	ps	SEE SHT. 26			
		2	ps	SEE SHT. 26			
		2	ss	SEE SHT. 26			
		4	ss	SEE SHT. 26			
		2	ss	SEE SHT. 26			

GIRDER WT: 19,314

Vermont Agency of Transportation
RECEIVED

CK'D BY GFR OK'D BY
05/15/2012
RESUBMIT APPROVED X
BY C. CARLSON DATE 05/16/2012

SEE .dxf FILES FOR WEB R CUTTING
SEE SHEET 26 FOR PIECE DETAILS
SEE SHEET B1 FOR NOTES

FINISH	MATERIAL	ASHTO M270 (ASTM A709) GRADE 50
HOLES	15/16" U.O.H.	
ELECTRODES		
WELDS	PER WPS	
SURFACE PREP	5/15/12	PER APPROVAL JAC
	NO DATE DESCRIPTION	BY

ARC
ADVANCED RESOURCES & CONST. ENTERPRISES, INCORPORATED
P.O. BOX 120 KINGFIELD, ME 04947
PHONE: (207) 265-2040 - FAX: (207) 265-4054

STRINGER DETAILS

DRAFTER	JAC	CONTRACT NO.	BR0 1449 (25)
DATE	4/11/12	VERMONT AGENCY OF TRANSPORTATION, MEMPHIS CITY, CO. OF OLEANS	DRG. NO.
CHECKED	JS	RAILROAD SQUARE, DIST. (CLASS 2) WATER COLLECTOR, BRIDGE NO. 8	
JOB #	12-100	G.C. REED & REED	9