STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET # 2

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

				EROSION CONTROL	NO FEDERAL/STATE PARTICIPATION	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
				-	-	3	3	EA	CHANGING ELEVATION OF SEWER MANHOLE	604.42	-
				-	-	6	6	EA	CAST IRON GRATE WITH FRAME, TYPE D	604.47	-
				-	-	4	4	EA	CAST IRON GRATE WITH FRAME, TYPE E	604.48	-
				-	-	645	645	m	150 mm UNDERDRAIN	605.10	2
				-	-	10	10	m	150 mm UNDERDRAIN CARRIER PIPE	605.20	-
				-	-	10	10	EA	UNDERDRAIN FLUSHING BASINS	605.95	-
				-	-	10	10	HR	POWER GRADER RENTAL	608.15	EST.
				-	-	10	10	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
				-	-	10	10	HR	POWER BROOM RENTAL	608.30	EST.
				-	-	10	10	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
				-	-	10	10	HR	TRUCK RENTAL	608.37	EST.
				-	-	10	10	HR	LOADER RENTAL, TYPE I	608.40	EST.
				-	-	560	560	m^3	DUST CONTROL WITH WATER	609.10	-
				-	-	2	2	m^3	STONE FILL, TYPE I	613.10	-
				10	-	-	10	m^3	STONE FILL, TYPE I (MOD. - INLET PROTECTION)	613.10	-
				-	-	420	420	m^2	PORTLAND CEMENT CONCRETE SIDEWALK, 125 mm	618.10	4
				-	-	525	525	m^2	BRICK PAVING	618.20	3
				-	-	2	2	m^2	DETECTABLE WARNING SURFACE	618.30	-
				-	-	4	4	EA	YIELDING MARKER POSTS	619.17	-
				700	-	-	700	m	SNOW FENCE (MOD. - PDF)	620.70	-
				-	-	50	50	m	RELAYING SEWER PIPE (200mm DIA.)	628.30	EST.
				-	-	3	3	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
				-	-	120	120	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
				-	-	1000	1000	HR	FLAGGERS	630.15	EST.
				-	-	1	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
				-	-	1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
				-	-	1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
				-	-	1	1	LU	FIELD OFFICE - TELEPHONE (NOT A BID ITEM)	631.25	-
				-	-	1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
				-	-	1	1	LS	TRAFFIC CONTROL	641.10	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

VERMONT AGENCY OF TRANSPORTATION

CLOUGH, HARBOUR & ASSOCIATES
ENGINEERS, SURVEYORS, PLANNERS & LANDSCAPE ARCHITECTS
11 WINNERS CIRCLE ALBANY, NEW YORK, 12205

PROJECT NAME: OLD_BENNINGTON_____
PROJECT NUMBER: STP 1400(5)

FILE NAME: /pave/97d228/p97d228.dgn
PROJECT LEADER: _I.P.K._____
DESIGNED BY: _J.S.P._____
p97d228qs2.i

PLOT DATE: 05-MAY-2008 14:
DRAWN BY: C.A.K.____
CHECKED BY: D.E.G.____
SHEET _3_ OF 48