STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET

VAOT Metric

UNDERDRAIN

BEGIN STATION km + m	END STATION km + m	TYPE	POSITION	DIA. mm	LENGTH m	TRENCH EARTH m³	TRENCH ROCK m³	GRAN BKFILL m³	FB EA	MKR PST EA
1+052.2	1+160	U	RT	150	108	65			2	
1+054	1+106	U	LT	150	51	37			1	
1+095	1+160	U	LT	150	65	39			1	
1+160	1+185	U	LT	150	25	15			-	
1+160	1+224	U	RT	150	61	37			1	
1+186	1+227	U	LT	150	41	35			-	
1+233.4	1+237.5	C	RT/LT	150	9	6			-	
1+233.4	1+306	U	RT	150	73	59			1	
1+237.5	1+306	U	LT	150	69	42			2	
1+307	1+340	U	RT	150	33.6	49			-	
1+307	1+340	U	LT	150	33	20			-	
1+340	1+381	U	LT	150	41	25			1	
1+340	1+383	U	RT	150	43	23			1	
SUBTOTAL					643 (U)	457			10	
					9 (C)					
ROUNDING					2 (U)	-			-	
					1- (C)					
TOTAL					645 (U)	457			10	
					10 (C)					

BRICK PAVING

BEGIN STATION km + m	END STATION km + m	POSITION	LENGTH m	WIDTH mm	BRICK PAVING m²	CONC CL B m³	REINF STEEL kg	JOINT SEAL m
0+990	1+019	LT	29	750	22	3	233	2
1+051.5	1+160	RT	108.5	750	81	12	870	8
1+053	1+160	LT	107	750	80	12	858	7
1+160	1+340	LT	180	750	135	20	1443	11
1+160	1+340	RT	180	750	135	20	1443	11
1+340	1+381.5	LT	41.5	750	31	5	334	3
1+340	1+390	RT	50	750	38	6	402	4
SUBTOTAL					522	78	5583	46
ROUNDING					3	-	-	-
TOTAL					525	78	5583	46

SIDEWALK

BEGIN STATION km + m	END STATION km + m	POSITION	TYPE	LENGTH m	WIDTH mm	SWALK 125 mm m²	DETECT WARNING m²	REMARKS
1+040	1+160	LT	125	120	1200	144		
1+040.8		LT	125	1.5	1530	2	1	RAMP
1+160	1+340	LT	125	180	1200	216		
1+340	1+383	LT	125	43	1200	52		
1+382.3		LT	125	1.5	1530	2	1	RAMP
SUBTOTAL						416	2	
ROUNDING						4	-	
TOTAL						420	2	

BEGIN STATION km + m	END STATION km + m	POSITION LEFT m	POSITION RIGHT m	REMARKS

VERMONT AGENCY OF TRANSPORTATION

CLOUGH, HARBOUR & ASSOCIATES
ENGINEERS, SURVEYORS, PLANNERS & LANDSCAPE ARCHITECTS
11 WINNERS CIRCLE ALBANY, NEW YORK, 12205

PROJECT NAME: OLD_BENNINGTON_____
PROJECT NUMBER: STP 1400(5)

FILE NAME: /pave/97d228/p97d228.dgn
PROJECT LEADER: _T.P.K._____
DESIGNED BY: _J.S.P._____
p97d228id.i

PLOT DATE: 05-MAY-2008 14:
DRAWN BY: C.A.K.____
CHECKED BY: D.E.G.____
SHEET _5_ OF 48