STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET # 1

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 2.8	50 3.2	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
ELM STREET 2+015.0, LT	STOP	1	750	750	0.56 8/31						1			X 4.3		X		X															[SIGN ID CODE R1-1]		E-143
MONUMENT AVE 1+016.1, RT	STOP	1	750	750	0.56 8/31						1			X 4.3		X		X															[SIGN ID CODE R1-1]		E-143
1+050.0, LT	STOP	1	750	750	0.56 8/31						1			X 4.3		X		X															[SIGN ID CODE R1-1]		E-143
1+070.0, LT	H	1	600	600	0.36 8/31						1			X 4.7		X		X															[SIGN ID CODE D9-2]		E-132
	↑	1	525	375	0.20 8/31																													26	
1+082.0, RT	SPEED LIMIT 25	1	600	750	0.45 8/31						1			X 4.3		X		X															[SIGN ID CODE R2-1]		E-142
1+120.0, LT	SOUTHERN VERMONT COLLEGE ↑				8/31		1				1			NOT ~~X~~ USED		X		X															ERECT SALVAGED SIGN ON NEW POST	-	-
		KWA 8/31																																	
											m	m	m 24.3 22.1	m	m 24.3	m	EA	kg	kg	kg		kg	kg	kg	kg									
TOTALS					m^2 2.69	m^2	EA. 1	m^2			m ~~24.3~~ 22.1				m 24.3				kg	EA.	kg						EA.	EA.	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY SECTIONS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: OLD_BENNINGTON_____
PROJECT NUMBER: STP 1400(5)

FILE NAME: /pave/97d228/p97d228.dgn
PROJECT LEADER: _I.P.K._____
DESIGNED BY: _J.S.P._____
p97d228ss1.i _____

PLOT DATE: 05-MAY-2008 14:
DRAWN BY: C.A.K.____
CHECKED BY: D.E.G.____
SHEET _24 OF___46