

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
			ROADWAY	TRAINING	EROSION CONTROL	UTILITIES	UTILITIES - NON PART.	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
			3							3		EACH	PRECAST REINFORCED CONCRETE PIPE D1 WITH CAST IRON GRATE	604.25				
			2							2		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40				
			1							1		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412				
			3							3		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418				
			80							80		HR	POWER BROOM RENTAL, TYPE II	608.31				
			100							100		MGAL	DUST CONTROL WITH WATER	609.10				
								30		30		CY	STONE FILL, TYPE I	613.10				
								60		60		CY	STONE FILL, TYPE II	613.11				
			500							500		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28				
			325							325		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10				
			75							75		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11				
			50							50		SF	DETECTABLE WARNING SURFACE	618.30				
			1							1		EACH	STEEL MARKER POSTS	619.16				
			30							30		LF	REMOVAL OF EXISTING FENCE	620.55				
			64.5							64.5		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
						55	55			110		LF	SLEEVES FOR UTILITIES (2 X 24")	625.10				
						20				20		LF	PVC SEWER PIPE (10")	628.35				
						1				1		LS	TRANSFER TO NEW SYSTEM, SANITARY SEWER	628.42				
							241			241		LF	PLASTIC WATER PIPE, RIGID (8")	629.33				
							1			1		LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM	629.42				
						10	75			85		TON	CRUSHED STONE BEDDING	629.54				
			200							200		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
			600							600		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
				520						520		HR	EMPLOYEE TRAINEESHIP	634.10				
			1							1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
			1							1		LS	TRAFFIC CONTROL	641.10				
			1200							1200		LF	4 INCH WHITE LINE	646.20				
			1200							1200		LF	4 INCH YELLOW LINE	646.21				
			40							40		LF	CROSSWALK MARKING	646.31				
			125							125		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
								175		175		SY	GEOTEXTILE UNDER STONE FILL	649.31				
					250					250		SY	GEOTEXTILE FOR SILT FENCE	649.51				
					25					25		LB	SEED	651.15				
					40					40		LB	FERTILIZER	651.18				
					1					1		TON	AGRICULTURAL LIMESTONE	651.20				
					1					1		TON	HAY MULCH	651.25				

PROJECT NAME: JOHNSON
 PROJECT NUMBER: BHO 1448(29)
 FILE NAME: z98j372qs.dgn PLOT DATE: 02/18/2009
 PROJECT LEADER: J.W. TUCKER DRAWN BY: A.P. GUYETTE
 DESIGNED BY: A.P. GUYETTE CHECKED BY: E.P. DETRICK
 QUANTITY SHEET #2 SHEET 5 OF 68