



BILL OF MATERIAL							
SHIP MARK	QTY	PIECE MARK	DESCRIPTION	LENGTH		REMARKS	PAGE LINE
				FT	IN		
12G1A	1		GIRDER				
	1	WP12a	PL 5/8 x 33 1/2	55	3 1/8	(CVN)	1 1
	1	WP12b	PL 5/8 x 33 1/2	36	7 1/2	(CVN)	1 3
	1	TF12a	PL 1 x 16	54	3 1/8	(CVN)	1 5
	1	TF12b	PL 1 x 16	37	7 1/8	(CVN)	1 6
	1	BF12a	PL 1 1/2 x 16	54	2 1/8	(CVN)	1 9
	1	BF12b	PL 1 1/2 x 16	37	7 1/8	(CVN)	1 10
	3	p1	PL 1 x 8	2	9 1/2	(CVN)	1 8
	1	p2	PL 1 x 8	2	9 1/2	(CVN)	1 8
	4	p4	PL 1/2 x 7	2	9 1/2	(CVN)	1 13
	2	p6	PL 1/2 x 7	2	9 1/2	(CVN)	1 13
	2	p8	PL 1/4 x 3 1/2	0	11		3 7

RECEIVED
 OK'D BY JFL OK'D BY EMM
 JUL 23 2011
 R. CUMMINS APPROVED
 BY EMM DATE 7/21/11

REVISIONS			PRINT RECORD		
NO	DATE	DESCRIPTION	DATE	QTY	ISSUED
			7-16	Sp	Appr
7-14-09		ADDED BRG STIFFS @ ABUT, ADDED SECT D, REMOVED WELD & REV TO GRIND TO BEAR IN SECT A			

MEGQUIER & JONES INC.
 STRUCTURAL STEEL SINCE 1895
 1156 BROADWAY
 SOUTH PORTLAND, MAINE 04106

PAINT	SSPC-SP10	HOLES U N	WELD U N.	Q C REVIEW
PROJECT	TH NO.1 OVER THE GIHON RIVER PROJECT NO. BHO 1448 (29) BRIDGE NO. 5 TOWN OF JOHNSON, VERMONT			DATE 6-8-09
DESCRIPTION	GIRDER ~ 12G1A			CHK'D BY GDC
ARCH	N/A	ENGR	VERMONT AGENCY OF TRANSPORTATION	JOB NO J-81
CUSTOMER	S.D. IRELAND CONCRETE CONSTRUCTION CORP.			SHT NO 12

- NOTES:**
- FOR GIRDER STANDARDS, SEE SHT. NO. 11.
 - FOR CAMBER DIAGRAM, SEE SHT. NO. 1.
 - FOR GENERAL NOTES, SEE SHT. NO. GN1.

