



- NOTE:
- THIS CONTRACT IS BASED UPON THE CONTRACTOR SETTING AND SPACING THE ANCHOR BOLTS TO THE MEASUREMENTS SHOWN ON THE APPROVED SHOP DRAWINGS. THE L.B. FOSTER CO. WILL NOT BE RESPONSIBLE FOR WORK NECESSITATED BY ANY OTHER SETTING AND SPACING.
 - THIS DRAWING IS NOT TO SCALE.
 - LENGTH OF RAILING ON THIS SHEET IS 25 LF PAY LENGTH.
 - POST SPACING IS MEASURED HORIZONTALLY ALONG FF OF RAILING.
 - SPLICE GAP AT SLEEVE = 1 1/2" TYP.
 - * RAIL LENGTHS DO NOT INCLUDE GAPS.
 - COMPENSATION FOR VERTICAL CURVE HAS BEEN INCLUDED IN RAIL LENGTHS

ANODIZED
 ● (FOR ANODIZING SPECS SEE LB1)

BRIDGE No. 5
 PROJECT No. BHO 1448 (29) ITEM No: 900-640

APPROVED: _____	REC'D APPROVAL _____
DRAWING _____	
L.B. FOSTER COMPANY	
1016 GREENTREE ROAD PITTSBURGH, PENNSYLVANIA 15220	
FOR: F. R. LAFAYETTE, INCORPORATED	
VERMONT AGENCY OF TRANSPORTATION	
TOWN OF JOHNSON, COUNTY OF LAMOILLE	
APPROACH RAILING FOR TH No 1 OVER THE GHON RIVER	
3L ALUM BRIDGE APPROACH RAILING ~ ELEVATION VIEWS	
MADE CMS DATE 10/24/09	JOB No. ARO573 CUST. No.
CHECK BLJ DATE 11/06/09	DRAWING LB2 REV. No.

REV.	DESCRIPTION	BY	DATE