

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							150				150		CY	COMMON EXCAVATION	203.15				
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
							81		15		96		CY	STRUCTURE EXCAVATION	204.25				
							41		15		56		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
							175				175		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
							140				140		CY	SUBBASE OF GRAVEL	301.15				
							2				2		CWT	EMULSIFIED ASPHALT	404.65				
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
									59		59		CY	CONCRETE, HIGH PERFORMANCE CLASS A	501.33				
									9		9		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
									44610		44610		LB	STRUCTURAL STEEL, ROLLED BEAM	506.50				
									976		976		LB	REINFORCING STEEL	507.15				
									112		112		LF	DRILLING AND GROUTING DOWELS	507.16				
									13520		13520		LB	EPOXY COATED REINFORCING STEEL	507.17				
									1		1		LS	SHEAR CONNECTORS (592 - 7/8" x 7")	508.15				
									8		8		GAL	WATER REPELLENT, SILANE	514.10				
									24		24		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
									172		172		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
									150		150		LF	BRIDGE RAILING, GALVANIZED HDSB/FASCIA MOUNTED/HAND RAIL	525.43				
									153		153		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
									1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
									8		8		EACH	BEARING DEVICE ASSEMBLY, PREFORMED FABRIC PAD	531.10				
									2		2		SY	REPAIR OF CONCRETE SUBSTRUCTURE SURFACE, CLASS I	580.13				
							10				10		CY	STONE FILL, TYPE I	613.10				
							19				19		LF	TREATED TIMBER CURB	616.35				
							50				50		LF	REMOVING AND RESETTING FENCE	620.50				
							169				169		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215				
							3				3		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
							85				85		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							40				40		LF	TEMPORARY TRAFFIC BARRIER	621.90				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL	641.10				
							441				441		LF	4 INCH WHITE LINE	646.20				
							441				441		LF	4 INCH YELLOW LINE	646.21				
							30				30		SY	GEOTEXTILE UNDER STONE FILL	649.31				

PROJECT NAME: CLARENDON
PROJECT NUMBER: BHO 1443 (39)

FILE NAME: ...05-07-quantity sheet.dgn PLOT DATE: 7/2/2009
PROJECT LEADER: MJC DRAWN BY: ENA
DESIGNED BY: SEB CHECKED BY: MJC
QUANTITY SHEET 1 SHEET 5 OF 24

