



**EROSION CONTROL NOTES**

1. THE CONTRACTOR SHALL INSTALL SILT FENCE AND HAY BALES FOR EROSION CONTROL AS LOCATED ON THE PLANS, PRIOR TO CONSTRUCTION. ALL SUCH INSTALLATION SHALL BE WITHIN THE EXISTING R.O.W.
2. THE CONTRACTOR SHALL LOAM, SEED, FERTILIZE AND MULCH ALL DISTURBED AREAS, EXCEPT ROADWAY AND SHOULDERS PRIOR TO THE COMPLETION OF THE PROJECT.
3. REFER TO STANDARD T-1 AND T-2 FOR ADDITIONAL DETAILS.

DATUM	
VERTICAL	LOCAL
HORIZONTAL	LOCAL

**LEGEND**

EXISTING EDGE OF RIVER	---
EXISTING TRAVELED WAY	----
PROPOSED TRAVELED WAY	----
ROW	----
GUARD RAIL	○—○
CULVERT	—
UTILITY POLE	□
TELEPHONE POLE	◇
TREES	⊗
TREE LINE	~~~~~
SILT FENCE	—□—

REVISIONS		
NO.	DESCRIPTION	BY & DATE

**DuBois & King INC.**

engineering    planning    management    development

<b>STATE OF VERMONT</b>			
<b>AGENCY OF TRANSPORTATION</b>			
Town Of	CHESTER	Bridge No.	11
Highway No.	TH 5	Log Sta.	-
		Surv. Sta.	-
<b>CHURCH STREET OVER WILLIAMS RIVER</b>			
<b>EROSION CONTROL SHEET</b>			
Designed By	B. C. AUSTIN	Drawn By	G. J. WOJCIECHOWSKI
Checked By	J. TUCKER	Date	03/01
		Bridge Design Supervisor	J. TUCKER
		Date	03/01
PROJECT	CHESTER	PROJECT NO.	BHO 1442 (32)
I.G.C. Info.	...zj365EC9.dgn		
D & K DWG NO.	11352	Sheet	9 of 22