

STATE OF VERMONT AGENCY OF TRANSPORTATION														QUANTITY SHEET #2								
SUMMARY OF ESTIMATED QUANTITIES														TOTALS			DESCRIPTIONS		DETAILED SUMMARY OF QUANTITIES			
TRAINING	FULL C.E. TRAIN	ADJUNCT	EROSION CONTROL	ADJUSTMENT No. 1	ADJUSTMENT No. 2	DECK	BRODE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS						
		10							90		SF	DETECTABLE TRAVELING SURFACE	818.30									
									90		LF	TEMPORARY TRAFFIC BARRIER	821.90									
									1		LS	FIELD OFFICE, ENGINEERS	831.10									
									1		LS	TESTING EQUIPMENT, CONCRETE	831.16									
									1		LS	TESTING EQUIPMENT, BITUMINOUS	831.17									
									1		LU	FIELD OFFICE TELEPHONE (N.A.B.)	831.25									
500									500		HR	EMPLOYEE TRAINESHIP	834.10									
									1		LS	MOBILIZATION/DEMOLITION	835.11									
									1		LS	TRAFFIC CONTROL	841.10									
						200	200	200	610		LF	DURABLE 4 INCH WHITE LINE	846.400									
						200	200	200	900		LF	DURABLE 4 INCH YELLOW LINE	846.410									
									36		LF	DURABLE 6 INCH WHITE LINE	846.420									
									95		LF	DURABLE CROSSHAJK MARKING	846.500									
									102		LF	TEMPORARY 8 INCH WHITE LINE	846.640									
									54		LF	TEMPORARY 24 INCH STOP BAR	846.680									
									4		EACH	TEMPORARY LETTER OR SYMBOL	846.690									
									149		LF	PAINTED CURB	846.81									
									215		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	848.85									
									80		SY	GEOTEXTILE FOR SFT FENCE	849.41									
									220		SY	GEOTEXTILE FOR FILTER CURTAIN	849.61									
									10		LB	SEED	851.15									
									1		TON	HAY/MULCH	851.35									
									1		LS	EPSC PLAN	852.10									
									80		HR	MONITORING EPSC PLAN	852.20									
									1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.)	852.30									
									430		SY	TEMPORARY EROSION MATTING	853.20									
									2		CV	TEMPORARY STONE CHECK DAM, TYPE I	853.35									
									40		CV	VEHICLE TRACKING PAD	853.35									
									1		EACH	INLET PROTECTION DEVICE, TYPE I	853.40									
									1		EACH	FILTER BAG	853.45									
									180		LF	BARRIER FENCE	853.50									
									540		LF	PROJECT DEMARCATION FENCE	853.55									
									1		EACH	TRANSPLANTING SHRUBS (2')	855.50									
									2		EACH	REMOVING SIGNS	875.50									
									2		EACH	ERECTING SALVAGED SIGNS	875.60									
									1		EACH	SETTING SALVAGED POSTS	875.61									
									1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	878.40									
									3		EACH	TEMPORARY DETECTOR	878.42									
									1		EACH	SPECIAL PROVISION (GRASS OUTLET SEDIMENT TRAP)	900.620									
									50		EACH	SPECIAL PROVISION (GRAVE, BARR)	900.630									
									80		LF	SPECIAL PROVISION (BOX BEAM GUARD RAIL, TRUSS)	900.640									
									222		LF	SPECIAL PROVISION (BRIDGE RAILING, TRUSS)	900.641									
									31		LF	SPECIAL PROVISION (METAL HAND RAILING)	900.642									

PROJECT NAME: RICHFORD
PROJECT NUMBER: BHF 0302 (3) S
FILE NAME: rich-quant.xls PLOT DATE: 10/2008
PROJECT LEADER: MJC DRAWN BY: AET
DESIGNED BY: SEB CHECKED BY: MJC
QUANTITY SHEET #2 SHEET 8 OF 41