

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
						1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1				1		LS	TRAFFIC CONTROL	641.10				
						380				380		LF	4 INCH YELLOW LINE	646.21				
						930				930		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
						485				485		LF	TEMPORARY 4 INCH YELLOW LINE	646.610				
						45				45		LF	TEMPORARY 24 INCH STOP BAR	646.680				
						12				12		EACH	TEMPORARY LETTER OR SYMBOL	646.690				
							130			130		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							25			25		LB	SEED	651.15				
							125			125		LB	FERTILIZER	651.18				
							1			1		TON	AGRICULTURAL LIMESTONE	651.20				
							1			1		TON	HAY MULCH	651.25				
							15			15		CY	TOPSOIL	651.35				
							1			1		LS	EPSC PLAN	652.10				
							80			80		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							20			20		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
							25			25		CY	VEHICLE TRACKING PAD	653.35				
							650			650		LF	PROJECT DEMARCATION FENCE	653.55				
						9				9		SF	TRAFFIC SIGNS, TYPE A	675.20				
						15				15		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						1				1		EACH	REMOVING SIGNS	675.50				
								14		14		SY	SPECIAL PROVISION (REMOVAL AND DISPOSAL OF ASPHALTIC ASBESTOS)	900.675				

PROJECT NAME: **STOWE**  
PROJECT NUMBER: **BHO 1446 (30)**  
FILE NAME: z99j244qs.dgn  
PROJECT LEADER: J.W. TUCKER  
DESIGNED BY: R.H. BARNES  
QUANTITY SHEET #2

PLOT DATE: 10/21/2009  
DRAWN BY: R.H. BARNES  
CHECKED BY: E.P. DETRICK  
SHEET 4 OF 37