



**KEYED NOTES**

ITEM	DESCRIPTION
1	WATER HEATER TO BE REMOVED AND PROPERLY DISPOSED. FRAMEWORK TO BE USED FOR TEMPORARY EQUIPMENT SUPPORT DURING CONSTRUCTION OF NEW FLOOR. REMOVE FRAMEWORK AND DISPOSE AFTER NEW FLOOR IS INSTALLED.
2	REMOVE AND DISPOSE EXISTING BOILER CONTROLS.
3	MOVE TELEPHONE OUTLET 24" FROM PANEL P-5 TO ALLOW INSTALLATION OF NEW PANEL P-6. (N.I.C.)
4	EXISTING 400 AMP SERVICE ENTRANCE SWITCH TO BE REMOVED. PROVIDE 18 X 18 X 8 J/B. PROVIDE CONDUIT/WIRE FROM J/B TO NEW SERVICE ENTRANCE SWITCH. (N.I.C.)
5	REMOVE AND DISPOSE EXISTING BOILER SYSTEM, EXPANSION TANK AND PIPING.
6	EXISTING ELECTRIC SERVICE, PANELS, METERS, SWITCHES TO BE REMOVED. DISCONNECT AND REMOVAL OF EXISTING ELECTRICAL SERVICE TO BE SCHEDULED SUCH THAT THERE IS NO INTERRUPTION OF EXISTING TENANT ACTIVITIES. (N.I.C.)
7	TELEPHONE CABLE AND SPLICE TO BE MOVED AND NEW SERVICE SPLICE INSTALLED BY NEW ENGLAND TELEPHONE. CO-ORDINATE WITH NEW ENGLAND TELEPHONE. (N.I.C.)
8	EXISTING PANEL P-5.
9	WATER SOFTENER AND WATER SOFTENER BRINE TANK TO BE DISCONNECTED AND TEMPORARILY INSTALLED ON PLATFORM ABOVE LEVEL OF NEW FLOOR AND THEN RE-INSTALLED AFTER NEW FLOOR IS INSTALLED.
10	WELL X-TROL TO BE REMOVED, TEMPORARILY INSTALLED ABOVE LEVEL OF NEW FLOOR AND RE-INSTALLED AFTER NEW FLOOR IS INSTALLED.
11	POWER TO SUBMERSIBLE PUMP AND WATER SERVICE FROM PUMP - 1" WATER SERVICE AND ELECTRIC TO PUMP TO BE EXTENDED TO ABOVE NEW FLOOR LEVEL. INSTALL PRES. SWITCH, PUMP STARTER, SHUT OFF VALVES ABOVE NEW FLOOR LEVEL.
12	DISCONNECT EXISTING ELEC. HMH. TEMPORARILY INSTALL IN STORAGE ROOM. DISCONNECT & REMOVE TEMPORARY ELECTRIC & PIPING AFTER WM-3 IS IN SERVICE.
13	REPLACE EXISTING LIGHT FIXTURE WITH KEYSTONE CR248-HO-A OR EQUAL. 2-F48T12/CW/HO LAMPS. (N.I.C.)
14	WATER SOFTENER - PROVIDE 120 V DUPLEX SURFACE MTD. 48" AFF.
15	HEAT CIRCUATOR PUMPS P1, P2 & P3. PROVIDE POWER WIRING AND SAFETY SWITCHES. REFER TO MECHANICAL PLANS.
16	EXISTING EMERGENCY LIGHT, LIGHT SWITCH, CONDUIT AND WIRING TO BE RELOCATED TO ALLOW DOORWAY TO BE RAISED 3 FEET. (N.I.C.)

**LEGEND**

- LUMINAIRES**
- FLUORESCENT LIGHT
  - CEILING LIGHT
  - WALL LIGHT
  - WALL LIGHT
  - EXIT LIGHT - WALL
  - EMERGENCY LIGHT - DOUBLE HEAD
- WALL SWITCHES**
- \$ SWITCH + 50" AFF
  - \$<sub>3</sub> THREE WAY SWITCH
  - \$<sub>FM</sub> FIREMATIC SWITCH - AT CEILING
  - \$<sub>M</sub> MANUAL MOTOR STARTER
  - \$<sub>OB</sub> OIL BURNER SAFETY SWITCH
  - \$<sub>OP</sub> SWITCH W/ PILOT LIGHT
  - \$<sub>SP</sub> SWITCH - SPEED CONTROL

**WALL RECEPTACLES**

- ⊕ DUPLEX OUTLET +24" AFF
- ⊕ SPLIT WIRED DUPLEX OUTLET
- ⊕ SINGLE SPECIAL PURPOSE OUTLET
- ⊕ DUPLEX OUTLET +50" AFF

**MISCELLANEOUS EQUIPMENT**

- ⊗ MOTOR STARTER
- SAFETY SWITCH
- PUSH BUTTON STATION
- ELECTRIC PANEL BOARD
- MOTOR
- ⊕ TIME SWITCH
- ⊕ BRANCH CIRCUIT

**ABBREVIATIONS**

- AFF ABOVE FINISHED FLOOR
- EC ELECTRICAL CONTRACTOR
- ES EQUIPMENT SUPPLIER
- GC GENERAL CONTRACTOR
- MC MECHANICAL CONTRACTOR
- PC PLUMBING CONTRACTOR
- GR GROUND
- GRC GALVANIZED RIGID CONDUIT
- JB JUNCTION BOX
- MOD MOTOR OPERATED DAMPER
- TTB TELEPHONE TERMINAL BOARD



**Pearson & Associates**  
MECHANICAL & ELECTRICAL ENGINEERS

P.O. BOX 610 STOWE, VERMONT 05672  
TEL. (802) 253-9607 FAX (802) 253-9290

STATE OF VERMONT  
DEPARTMENT OF STATE BUILDINGS  
AGENCY OF ADMINISTRATION  
MONTPELIER, VERMONT

E. F. KNAPP AIRPORT TERMINAL  
MECHANICAL RENOVATIONS  
BERLIN, VERMONT

DATE: 9/06/91	SCALE: AS SHOWN	REVISIONS: DWG NO.
DRAWN BY: B.W.M.	APPROVED BY: E.E.P.	5/12/92 36