QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
90	CY	COMMON EXCAVATION	203.15	
1150	CY	GRANULAR BORROW	203.32	
720	CY	TRENCH EXCAVATION	204.20	
62	LF	12" CSP	601.0006	
14	LF	15" CSP	601.0011	
1	EACH	12" CSPES	601.6005	
2	EACH	15" CSPES	601.6010	
3	EACH	PRC PIPE D.I.w/C.I. GRATE OR COVER	604.25	
1770	LF	6" UNDERDRAIN	605.10	
60	LF	12" UNDERDRAIN	605.13	
7	EACH	UNDERDRAIN FLUSHING BASIN	605.95	
16	SY	GEOTEXTILE FOR SILT FENCE	649.51	
180	LB	SEED	651.15	
2.5	TON	MULCH	651.25	
8	EACH	HAY BALES FOR EROSION CONTROL	651.26	
485	CY	REHANDLE TOPSOIL	651.36	
1	EACH	WIND CONE (L-107)	864.0	
12	EACH	RUNWAY END LIGHTS, (L-125)	864.0	
30	EACH	MIRL's BASE MOUNTED, (L-125)	864.0	
4	EACH	REIL's, (L-125)	864.0	
69	EACH	MITL's BASE MOUNTED, (L-125)	864.0	
1	EACH	PAPI, (L-125)	864.0	
12	EACH	TAXIWAY GUIDANCE SIGNS, (L-125)	864.0	
220	LF	TWO-WAY x 4" CONC. ENCASED DUCT (L-110)	864.0	
215	LF	FOUR-WAY x 4" CONC. ENCASED DUCT (L-110)	864.0	
90	LF	SIX-WAY x 4" CONC. ENCASED DUCT (L-110)	864.0	
11350	LF	CABLE TRENCH (L-108)	864.0	
14000	LF	SCHEDULE 40 PVC CONDUIT (L-110A)	864.0	
16275	LF	UNDERGROUND CABLE, IN CONDUIT (L-108)	864.0	
11900	LF	COUNTERPOISE WIRE, IN TRENCH (L-108)	864.0	
3	EACH	BEACON TOWERS (L-103)	864.0	
2	EACH	HAZARD BEACON (L-102)	864.0	
1	EACH	ROTATING BEACON (L-101)	864.0	
	LS	ELECTRICAL SERVICE OVERHEAD	864.0	
1	EACH	ELECTRICAL HANDHOLE (L-108)	864.0	
	LS	AIRPORT LIGHTING CONTROLS (L-125.1)	864.0	
	LS	ELECTRIC ROOM & EQUIPMENT (L-109)	864.0	
2	EA	CONSTANT CURRENT REGULATORS (L-828)	864.0	

APPROXIMATE SUMMARY OF QUANTITIES

QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING

PROJECT NAME CALEDONIA COUNTY STATE AIRPORT
PROJECT NUMBER AIR 04-3032

D&K NO. N12603
SHEET 2 OF 14 SHEETS