QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.
0.5	ACRE	CLEARING AND GRUBBING	201.11
2	EA	DEMOLITION AND DISPOSAL OF BUILDING	202.10
2800	CY	COMMON EXCAVATION	203.15
750	CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28
4100	SY	FINE GRADING-SUBGRADE	203.40
1300	CY	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.26
6	CWT	EMULSIFIED ASPHALT	404.65
700	TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.25
23	CY	CONCRETE, CLASS B	501.25
1100	LB	REINFORCING STEEL	507.15
5	GAL	WATER REPELLENT	514.10
1	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I (NOT A BID ITEM)	608.25
1	HR	TRUCK RENTAL (NOT A BID ITEM)	608.37
8	MGAL	DUST CONTROL WITH WATER	609.10
1	LS	TESTING EQUIPMENT - CONCRETE	631.16
1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17
1	LS	MOBILIZATION	635.10
350	SY	GEOTEXTILE FOR SILT FENCE	649.51
75	LB	SEED	651.15
450	LB	FERTILIZER	651.18
2	TON	AGRICULTURAL LIMESTONE	651.20
2	TON	HAY MULCH	651.25
100	EA	HAY BALES FOR EROSION CONTROL	651.26
500	CY	TOPSOIL	651.35
10	EA	EVERGREEN TREES	656.20
1	LS	ROADSIDE REST FACILITY (MOD.) (3 SALT/SAND SHEDS 40' x 84')	658.15

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS		FEET	MILES	REMARKS
FROM	TO				+	-			
TOTALS									

DATE PLOTTED: 10 FEB 2000

PROJECT NAME LONDONDERRY SALT SHED
PROJECT NUMBER STP SALT(15)