

GENERAL NOTES:


- 1) REMOVE AND REPLACE SOME OF THE 2" INSULATION THAT IS WET. THIS WILL BE DONE BY TIME AND MATERIALS.
- 2) HOURLY RATES APPLIED TO THESE COSTS WILL BE IN ACCORDANCE WITH THE HOURLY RATE SCHEDULE SUBMITTED AT TIME OF BID, SUBJECT TO VERIFICATION BY THE OWNER OR THE OWNER'S REPRESENTATIVE.
- 3) EXISTING MEMBRANE AND FLASHING TO BE REMOVED AND DISPOSED OF. EXISTING INSULATION TO BE PROTECTED AND REMAIN IN PLACE. INSTALL NEW 5/4" PRESSURE TREATED NAILERS WHERE INDICATED. 1" NEW RIGID INSULATION AND NEW .060 EPDM MEMBRANE ROOFING SYSTEM WITH METAL FLASHING.
- 4) ALL BLOCKING, CANT STRIPS, & LUMBER TO BE PRESSURE TREATED AND REPLACED AS REQUIRED.
- 5) DETAILS ARE EXAMPLES ONLY. ACTUAL INSTALLATION TO BE DONE IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
- 6) ALL MATERIAL REMOVED SHALL BE PROPERLY AND LEGALLY DISPOSED OF.
- 7) FIELD VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS.
- 8) NEW INSULATION TO BE LOOSE LAID TO COMPLY WITH ROOFING MANUF. RECOMMENDATIONS.
- 9) NEW EPDM .060 REINFORCED MEMBRANE TO BE MECHANICALLY FASTENED TO COMPLY WITH ROOFING MANUF. RECOMMENDATIONS.
- 10) NEW EPDM .060 REINFORCED MEMBRANE SHALL BE COLOR: WHITE
- 11) CONTRACTOR TO PROVIDE A 15 YEAR TOTAL ROOFING SYSTEM WARRANTY INCLUDING: INSULATION, MEMBRANE, FLASHING, ADHESIVES, FASTENERS, ETC. WARRANTY TO BE PROVIDED BY PRIMARY MANUFACTURER.



AGENCY OF TRANSPORTATION
CASTLETON 4 BAY GARAGE
REROOF PLAN & DETAILS



STATE OF VERMONT
Department of Buildings
and General Services
Agency of Administration
Montpelier, Vermont



REVISIONS

SCALE: AS SHOWN
DATE: JULY, 2001
DRAWN BY: N. HERSEY
APPR. BY: R. BARRY

AOT GABARGE
CASTLETON
4 BAY GARAGE
REROOF DETAILS